

Lloyd's Register of Shipping.

MAR 27 1940

Ship's Name "ELMCREST," ex "Jagled"Official No. ✓

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in October, 1932.

Cardiff, March 1940.

brews accommodation in forecabin now removed, and new accommodation provided in poop space.

Companionway on forecabin deck removed, and hole in deck blanked off.

FORECASTLE. One opening port side of forecabin bulkhead closed with riveted plate. One new opening cut at centre 40" wide x 4'-0 1/2", sill 2 1/2", fitted riveted channels and 3" storm boards.

Manhole to chain locker inside forecabin now blanked off, and hatchway to peak space fitted 9" B.P. coaming, bleats, wood cover, & battening arrangements provided.

POOP. Cargo hatchway in freeboard deck inside poop plated over in way of new accommodation.

Two openings in poop bulkhead plated over and two new openings made each 27" wide x 4'-6" x 2 1/2" sill, leading to new accommodation. Steel hinged doors (5/16") fitted, operable from both sides.

Pedestal for new gun mounting built at after end of poop deck hatchway, and remainder of hatchway planked over with 3" pine. Planks bolted, caulked, and painted. Two teak doors (1 5/8" thick, 24" wide, sill 18") fitted at after side of gun pedestal, giving access to new accommodation.

Ventilators. 5 vents on forecabin deck & 3 on poop dispensed with. Two 21" vents to lower hold on forecabin cropped below forecabin deck, & holes in freeboard deck plated over. 2 samson post vents on poop cropped 36" above deck.

4 new vents to poop accommodation 12" dia x 3/4" x 18".

2 - - - - - 6" dia, mushroom type.

2 - 6" dia. goosenecks to lavatories.

Wood plugs and canvas covers provided.

Side Scuttles in new accommodation provided with hinged deadlights of substantial construction.

Sanitary discharges. 2 port & 2 starboard 4" W.C. discharges with valve below freeboard deck now fitted in poop space.

Frank J. Richardson

Lloyd's Register of Shipping.

Ship's Name "ELMCREST," ex "Lyfied"Official No. ✓

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in

below.Bridge after bulkhead.

New opening made leading to gunner's room in
tween deck space. Framed teak door fitted, 24" wide
x 4'-0 1/2" x 1 5/8" thick. Sill 24" high. ✓

Noted

27/3/40

RETAIN