

(LLOYDS REGISTER.)

G. R. 130
Lloyds Register

VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyds Register of British and Foreign Shipping.

Signal Letters (if any) *T. Q. D. V.*

Official Number. 150349		Name of Ship. Canadian Traveller		No., Date, and Port of Registry. 7 - March, 12th - 1921 Montreal. Que.	
No., Date, and Port of Previous Registry (if any). First Registry					
Whether British or Foreign Built. British	Whether a Sailing or Steam Ship; and if a Steam Ship how propelled. Steam Screw	Where Built. Victoria. B.C.	When Built. 1921	Name and Address of Builders. Harbour Marine Co., Ltd., Victoria. B.C.	
Number of Decks ... Two		Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post ...		Feet. 399	Tenths 8
Number of Masts ... Two		Length at quarter of depth from top of weather deck at side amidships to bottom of keel ...		399	2
Rigged ... Schooner		Main breadth to outside of plank ...		52	28
Stern ... Elliptical		Depth in hold from tonnage deck to ceiling at midships ...		28	5
Build ... Clincher		Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards ...		-	-
Galleries ... None		Depth from top of beam amidships to top of keel ...		32	1
Head ... Straight		Depth from top of deck at side amidships to bottom of keel ...		31	24
Framework and description of vessel Steel "Freighter"		Round of beam ...		1	08
Number of Bulkheads ... Six		Length of engine room, if any ...		47	6
Number of water ballast tanks Seven		and their capacity in tons ... 1304 Tons			

PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel ... **10,800** Tons. Ditto per inch immersion at same depth ... **42** Tons.

PARTICULARS OF PROPELLING ENGINES, &c. (if any).

No. of sets of Engines.	Description of Engines.	Whether British or Foreign made.	When made.	Name and address of makers.	Reciprocating Engines. No. and Diameter of Cylinders in each set.	Length of Stroke.	Rotary Engines. No. of Cylinders in each set.	N. H. P. I. H. P. Speed of Ship.
One	Triple Expansion	Engines.	Engines.	Engines.	Three			266.5
		British	1921	John Inglis Co. Toronto. Ont.	27"	48"	-	3000
One	Scotch Marine	Boilers.	Boilers.	Boilers.	44"			
	Three	British	1921	Machinery Dept. Victoria, B.C.	73"			11½ Knots
	180 lbs							

PARTICULARS OF TONNAGE.

GROSS TONNAGE.		No. of Tons.	DEDUCTIONS ALLOWED.		No. of Tons.
Under Tonnage Deck ...		4882.11	On account of space required for propelling power		1741.64
Space or spaces between Decks...			On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew		
Turret or Trunk ...			These spaces are the following, viz.:—		
Forecastle ... Side Rooms		28.80	Rooms in Poop & Deck Houses		162.20
Bridge space ...		78.40			
Poop or Break ...		152.34			
Side Houses ...		36.11			
Deck Houses ...		123.87			
Chart House ...		5.74			
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894 ...		76.74	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:—		
Excess of Hatchways ...		58.51	Cubic Metres Chain Locker..... 9.36		
			F.P. Bos'n Store.... 8.75		
Gross Tonnage ...	5442.62	15402.61	A.P. Bos'n Store... 37.77		175.61
Deductions, as per Contra ...	2079.45	5884.84	Wireless... 8.41		
Registered Tonnage ...	3363.17	9517.77	Machinery Dept. 5.74		2079.45
			F.P. 1.50.57		

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is **658.40** tons, and the tonnage of the total spaces below the Upper Deck for propelling machinery and for light and air is **76.74** tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Bridge	297.50	Crew's W.C.....	12.66	Total Tonnage. 407.69
Galley.....	11.30	Upper Deck, Light & Air	46.72	
Wheel House....	5.32	Skylight.....	2.99	
Steering Engine.	31.20			

Name of Master	Certificate of { Service No. Competency No.
No. of Owners	
Name, Residence, and Description of Managing Owner if there are more owners than one.	
His Majesty represented by the Minister of Marine & Fisheries, Ottawa, Ontario.	
64 shares.	
Dated Montreal March 12th, 1921	



© 2020

Lloyd's Register
Foundation

W 389-0 139