

Boiler
endorsement

Shipbuilders: Messrs. ^{Wm} Donford

Yard No. 664

Makers: Messrs. ~~Stanton~~ ^{Stanton} Chemical Engineers & Shipbuilders

Boiler No. 6384

It is submitted that the plan of cylindrical multitubular boiler merits approval for a working pressure of 120 lbs per sq. ^{in.}, provided the boiler be constructed under the usual conditions of survey and testing.

The Steel Testing Surveyors should be advised regarding the tensile strength of the shell plates & butt straps

viz:- 29-33 tons/in²

+ the distances between the rows of rivets in the longitudinal seam be amended as shown in plan, & two additional screw stays be fitted to the position of four screw stays amended as shown in plan & the plan & ^{CHH}

Ltr 16/11

Return plan.

Retain copy.

[Signature] 10. 11. 39

W39-0273