

REPORT of SURVEY for REPAIRS, &c.

Date of writing Report 25 Aug 1927 When handed in at Local Office 19 Port of Rotterdam
 No. in Survey held at Schiedam Date, First Survey 29 July Last Survey 24 Aug 1927
 Reg. Book. 32361 on the Wool Iron or Steel S. S. PRERADOVIC (No. of Visits) 14

TONNAGE:— Built at Vegesack By whom Bremer Vulkan When 1907
 GROSS 5341 Owners Jugo's Lovensko Amerikanska Owners' Address Split
 UNDER DK. 5020 Managers " " " " (if not already recorded in Appendix to Register Book).
 NET 3418 Port belonging to Split

Surveyed Afloat or in Dry Dock? afloat Name of Dock River Haas Destined Voyage Cardiff
 WB=CellDBorDBa feet; uE&B feet; f feet } Particulars of Classification (which must be inserted
 total capacity tons. FPT tons; APT tons; MT feet tons. } precisely as in Register Book & Supplements).

N.B.—All alterations in the existing records should be underlined.
 If the Vessel has Water Ballast Tanks, state whether the manhole covers have been removed, and the insides of the tanks examined. Also state the amount of deterioration (if any) found in the thicknesses of the floors, framing, girders, and of the inner bottom plating, especially in the boiler space.

Last Report, No. Port

(Periodical Surveys, when held, must be reported in detail and verbatim in the terms of the Rules. State clearly the cause of Repairs, if any, and, in detail, the nature and extent of Examinations and subsequent repairs. Repairs on account of Damage (the cause of which must be stated) should be separated from Repairs due to other causes; and besides being detailed in the body of the report, should be summarised in the form shown below. Whenever the replacement of Anchors or Chains is reported, the particulars should be clearly stated in the space provided on the back of this form. State also the dates and initials of any letters respecting this case. M 25 July 1924
M 4 August 1924

In damage cases where the Surveyor has not made a special damage report he is required to state whether he offered his services for this purpose and to whom and why they were declined. Society's Freeboard (if assigned) as painted on Ship and now verified ft. in.

Was a damage report made by anyone else? If so, by whom?

REPAIRS, OR EXAMINATION AS PER RULE, FOR S/S N° 3 (cont. Lu. Report 91674) with a view to classification
N° 2 - 3 - 4 and 5 double bottom tanks cleared and cleaned examined
internally and found in a good condition, and coated as required
doubling plates under sounding pipes good.
Close ceiling in way of N° 2 and 5 double bottom tank removed, timber
boards lifted, tank top and bilges cleaned (except in permanent
cross bunker) examined and found in a good condition
N° 2 and 5 double bottom tank (except in way of cross bunker) and
fore and after peak tank tested as required by the Rules and
found tight
Engine and boiler room space examined and found in a

SUMMARY OF DAMAGE REPAIRS:—	Shell Plates.	Frames.	R. Frames.	Floors.	Beams.	Str. Plates.	Dk. Plates.	Other Items:—
Renewed								
Removed and Faired or Repaired								
Faired or Repaired in place								

PRESENT CONDITION OF THE			
Decks.....	<i>good</i>	State if Tanks have been examined inside.....	<i>yes</i>
Caulking of Decks.....	"	State if Tanks now tested.....	<i>as per report yes</i>
Coamings.....	"	Bulkheads.....	<i>good</i>
Beams & Fastenings.....	"	Ceiling.....	"
Outside Plating.....	<i>as far as end good</i>	Cement or Asphalt.....	"
Breasthooks.....	<i>good</i>	(State which) Rudder.....	<i>as far as end</i>
Transoms.....	"	Steering gear and its connections.....	<i>good</i>
Frames.....	"	Windlass.....	"
Reverse Frames.....	"	Have Pumps now been examined and found efficient?.....	"
Longitudinals.....	"	Have Sluice Valves now been examined and found efficient?.....	"
Transverses.....	"	Have Watertight Doors now been examined and found efficient?.....	<i>yes</i>
Floors.....	"	Have Ventilators and their Coamings been examined and found efficient?.....	<i>yes</i>
Keelsons.....	"		
Stringers.....	"		
Inner Bottom Plating.....	"		
		Dblng. Plates under Sounding Pipes.....	<i>good</i>
		Engine Room Skylights.....	"
		Coal Bunkers, Open'gs, Lids, &c.....	"
		Scuppers.....	"
		Cargo Hatchways.....	"
		Hatches.....	"
		Planking of Wood Vessels.....	
		Caulking.....	<i>ditto</i>
		Treenails.....	<i>ditto</i>
		Breasthooks & Stemson.....	<i>ditto</i>
		Transoms, Pointers, & Crutches.....	<i>ditto</i>
		Timbers of Frame at openings.....	<i>ditto</i>
		Ditto ditto at other places.....	<i>ditto</i>
		Stringers, Clamps & Shelves.....	<i>ditto</i>
		Salting.....	<i>ditto</i>
		(State if examined.)	
		Copper, or Y.M. of Wood Vessels.....	<i>✓</i>
		(State if on Feet). When put on, Month.....	<i>✓</i> Year <i>✓</i>
		Boats.....	<i>good</i>
		Masts, Yards, &c.....	"
		Condition, how ascertained.....	<i>end</i>
		(State if wedges removed).....	<i>no wedges</i>
		Sails.....	<i>✓</i>
		Equipment letter.....	
		Anchors, No. of.....	<i>Complete</i>
		Cables (State if now ranged).....	
		length.....	<i>as per Liverpool</i>
		(on board) Rule length.....	<i>report 91674</i>
		Hawser & Warps.....	<i>sufficient</i>
		Standing and Running Rigging.....	<i>good</i>

General Observations, Opinion as to Class, Recommendation, &c.:—

State clearly whether any and, if so, what alteration is suggested to be made in the existing classification and notification of the vessel in the Register Book consequent upon this survey, thus, for example:—"to remain as now classed in the Register Book without fresh record of Survey," "to remain as classed and to have record of survey 1,24," or "to remain as classed and to have record of survey, 1,24, and the notations of ss No. 1-24 and ptn24, &c."

The above is forwarded for the information of the Committee

RETAIN

Survey Fee (per Section 29) <u>no fee charged</u>	Fees applied for, <u>19</u>
Special Damage or Repair Fee (if any) <u>see first entry Report</u>	Received by me, <u>19</u>
Travelling Expenses (if chargeable) <u>✓</u>	
Second Surveyor's Fee (if any) <u>✓</u>	

Committee's Minute See J.E. Rpt
 Character Assigned Ret 16722
 Surveyor to Lloyd's Register of Shipping. H.P. Yonker
 FRI. 21 JUN 1929
 FRI. 18 MAY 1928
 FRI. 28 OCT 1927
 FRI. 24 AUG 1928
 TUES. 15 MAY 1928
 TUES. 22 MAY 1928
 FRI. 12 OCT 1928
 FRI. 28 JUN 1929
 TUE. 12 NOV 1929
 FRI. 28 JAN 1930
 TUE. 10 NOV 1931

Is Certificate required? If so, to be sent to

W394-0082

Windlass and Steam steering gear its connections rods
chains block rudder quadrant and hand steering gear
overhauled examined and found in a good condition
Hast spars, rigging examined and found good
Pumps water light doors air & sounding tubes examined and
made or found in order
Stoke hold bulk head examined and found repaired.

Lower side bunkers on SB & PS in engine room space
now containing coal, to clean and examine. Ceiling
in way to lift and tanks in way to test
Owners representative's stated same will be done on vessel's
arrival at Cardiff, where vessel is now proceeding
Tank top where locally wasted SB & PS in cross bunker
forward SB & PS door to cross bunker to repair

When Anchors or Cables are supplied, the particulars are to be reported in the following form:--

[illegible][illegible]

Shell plating has not been drilled.

H. P. Lonker