

Lloyd's Register of Shipping.

Ship's Name "FRANCES MASSEY"

Official No. 160060.


Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in JULY, 1932.

Shelter Deck: Tonnage opening 4'-1" x 18'-6" wide coaming 9 B.A.
3 fore and afters, 3 x 3 x 140 angles, double, spaced
evenly and riveted to lugs on coamings at their ends.
23 wood covers, thwartships, bearing 2½".
No cleats.

Upper Deck in poop to A.P. Tank.

Hatchway 6'-6" x 6'-6", coaming 12" x .40 steel.
Cover ⅝" steel plate, stiffener and riveted to coaming.
with W.T. access manhole.

(Swansea. Oct 1937)



© 2019

Lloyd's Register
Foundation

W395-0052.2