

Rpt. 13.

No. 49636

**REPORT ON ELECTRIC FITTINGS.**

(OTHER THAN FOR THE PROPULSION OF THE VESSEL)

30 OCT 1929

Date of writing Report 18.9.29 When handed in at Local Office 26.10.29 Port of GLASSGOW.

No. in Survey held at GREENOCK. Date, First Survey 2.9.29 Last Survey 12.9.29  
Reg. Book. S.S. ASPERITY. (Number of Visits 4)

39243 on the

Tons { Gross  
Net

Built at GREENOCK By whom built MESSRS G. BROWN &amp; CO Yard No. 170 When built 1929

Owners MESSRS F. T. EVERARD &amp; SON LTD Port belonging to LONDON.

Electric Light Installation fitted by MESSRS TELFORD GRIER &amp; MCKAY Contract No. 170 When fitted 1929

System of Distribution Two Wire

Pressure of supply for Lighting 110 volts, Heating — volts, Power — volts.

Direct or Alternating Current, Lighting Direct Power —

If alternating current system, state frequency of periods per second —

Has the Automatic Governor been tested and found efficient when the whole load is suddenly thrown on or off yes

Generators, do they comply with the requirements regarding rating yes, are they compound wound yes

are they over compounded 5 per cent. yes, if not compound wound state distance between each generator —

Where more than one generator is fitted are they arranged to run in parallel —, is an adjustable regulating resistance fitted in series with each shunt field yes

Are all terminals accessible, clearly marked, and furnished with sockets yes, are they so spaced or shielded that they cannot be accidentally earthed, short circuited, or touched yes

Are the lubricating arrangements of the generators as per Rule yes

Position of Generators Starboard Side of Main Engine Room.

is the ventilation in way of the generators satisfactory yes, are they clear of all inflammable material yes

if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the generators — and —, are the generators protected from mechanical injury and damage from water, steam or oil yes

are their axes of rotation fore and aft yes

Earthing, are the bedplates and frames of the generating plant efficiently earthed yes are the prime movers and their respective generators in metallic contact yes

Main Switch Boards, where placed on Bulkhead near Generator

If the generators and main switchboard are not placed in the same compartment, is each generator provided with a fuse on each insulated pole as near as possible to the terminals of the generator, additional to that provided on the main switchboard —

Switchboards, are they placed in accessible positions, free from inflammable gases and acid fumes yes

are they protected from mechanical injury and damage from water, steam or oil yes, if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the switchboards — and —

are they constructed wholly of durable, non-ignitable non-absorbent materials yes, is all insulation of high dielectric strength and of permanently high insulation resistance yes, if semi-insulating material is used, are all conducting parts insulated from the slab with mica or micanite or other non-hygroscopic insulating material, and the slab similarly insulated from its framework —

and is the frame effectively earthed yes. Are the fittings as per Rule regarding: — spacing or shielding of live parts yes, accessibility of all parts yes, absence of fuses on back of board yes, proportion of omnibus bars yes, individual fuses to voltmeter, pilot or earth lamp yes, connections of switches yes

Main Switchgear, description of switchgear for each generator and each outgoing circuit, and arrangement of equalizer switches

Double Pole Main Switch & fuses for Generator Circuit

Double Pole Switch & fuses for each outgoing circuit

Instruments on main switchboard one ammeter one voltmeter synchronising device for paralleling purposes.

Earth Testing, state what means are provided at the main switchboard for indicating the state of the insulation of the system

Lamp Switch & fuses in series between each bus bar & Earth.

Switches, Circuit Breakers and Fusible Cut-outs, do these comply with the requirements of the Rules yes

Joint Boxes Section and Distribution Boards, is the construction, protection, insulation, material, and position of these as per rule yes



© 2021

Lloyd's Register  
Foundation

W4-0218



Cables: Single, twin, concentric, or multicore single are the cables insulated and protected as per Tables IV or V of the Rules yes  
Fall of Pressure, state maximum between bus bars and any point of the installation under maximum load 5 volts  
Cable Sockets and other connections, are the ends of all cables having a sectional area of 0.04 square inch and above provided with soldering sockets yes  
Paper Insulated Cables, If cables are paper covered, is the dielectric at the exposed ends of the conductor protected from moisture by being suitably sealed with insulating compound none  
Cable Runs, are the cables fixed as far as possible in accessible positions not exposed to drip or accumulation of water or oil, or to high temperature from boilers, steam pipes, uptakes or other hot objects, or to avoidable risk of mechanical damage yes  
Support and Protection of Cables, state how the cables are supported and protected Lead covered in steel tubing or Lead covered Clipped to Bulkheads in Accommodation  
If cables are run in wood casings, are the casings and caps secured by screws —, are the cap screws of brass —, are the cables run in separate grooves —. If armoured and lead covered cables are secured by metal clips, are the clips spaced as per Table VIII yes  
Refrigerated Chambers, if lights are fitted, are the cables and fittings in accordance with the special requirements —  
Joints in Cables, state if any, and how made, insulated, and protected none  
Watertight Glands and Deck Tubes, are all cables passing through decks and watertight bulkheads provided with deck tubes or watertight glands yes  
Bushes in Beams and Non-watertight Partitions, where unarmoured cables pass through beams and non-watertight partitions, are the holes efficiently bushed yes state the material of which the bushes are made Lead  
Earthing Connections, state what earthing connections are fitted and their respective sectional areas —  
are their connections made as per Rule yes  
Alternative Lighting, are the groups of lights in the propelling machinery space arranged as per Rule yes  
Emergency Supply, state position and method of control of the emergency supply and how the generator is driven none  
Navigation Lamps, are these separately wired yes, controlled by separate switch and separate fuses yes, are the fuses double pole yes  
are the switches and fuses grouped in a position accessible only to the officers on watch yes  
has each navigation lamp an automatic indicator as per Rule yes  
Secondary Batteries, are they constructed and fitted as per Rule none  
Fittings, are all fittings on weather decks, in stokeholds and engine rooms and wherever exposed to drip or condensed moisture, watertight yes  
are any fittings placed in spaces in which goods are liable to be stacked in close proximity to them; if so, how are they protected none  
are any fittings placed in spaces where inflammable or explosive dust or gases are liable to be present, if so, how are they protected In double glass Watertight Wellglass Fittings.  
in W.I. Steel Tube. how are the cables led —  
where are the controlling switches situated outside of dangerous space  
Searchlight Lamps, No. of none, whether fixed or portable —, are their fittings as per Rule —  
Arc Lamps, other than searchlight lamps, No. of none, are their live parts insulated from the frame or case —, are their fittings as per Rule —  
Motors, are their working parts readily accessible none, are the coils self-contained and readily removable for replacement —  
are the brushes, brush holders, terminals and lubricating arrangements as per Rule —, are the motors placed in well-ventilated compartments in which inflammable gases cannot accumulate and clear of all inflammable material —  
are they protected from mechanical injury and damage from water, steam or oil — are their axes of rotation fore and aft —  
if situated near unprotected woodwork or other combustible material, are the motors of the totally enclosed, pipe ventilated, forced draught, drip or flame proof type —  
if not of this type, state distance of the combustible material horizontally or vertically above the motors — and —  
Control Gear and Resistances, are the generator field and motor speed regulators, starters and controllers constructed and fitted as per Rule yes  
Lightning Conductors, where lightning conductors are required, are these fitted as per Rule yes  
Ships carrying Oil having a Flash Point less than 150° F. Have the special requirements of the Rules been complied with regarding switches, joint boxes, section and distribution boards, protection of cables, method of distribution, lead of cables, lights and fittings yes  
If portable lamps for use in dangerous spaces are supplied, are they of a type approved by the Home Office yes

PARTICULARS OF GENERATING PLANT.									
DESCRIPTION OF GENERATOR.	No of	RATED AT				DRIVEN BY	WHERE DRIVEN BY AN INTERNAL COMBUSTION ENGINE.		
		Kilowatts.	Volts.	Ampères.	Revs. per Min.		Fuel Used.	Flash Point of Fuel.	
MAIN	one	3	110	27	1000	Enclosed Steam Engine			
AUXILIARY									
EMERGENCY									
ROTARY TRANSFORMER									

LIGHTING AND HEATING CONDUCTORS.									
Ref. No.	DESCRIPTION.	No. of Conductors.	Effective Area of each Conductor. Sq. Ins.	COMPOSITION OF STRAND.		Total Maximum Current. Amperes.	Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
				No.	Diameter.				
	MAIN GENERATOR	one	.01	4	.044	27	30	O.R.	L.C. & Steel Tube
	EQUALISER CONNECTIONS								
	AUXILIARY GENERATOR								
	EMERGENCY GENERATOR								
	ROTARY TRANSFORMER								
	AUXILIARY SWITCHBOARDS								
	ENGINE ROOM								
	BOILER ROOM								
	ACCOMMODATION								
	Navigation	one	.003	3	.036	3	210	O.R.	L.C. & Steel Tube
	Fore & Midship	one	.003	3	.036	5	160	O.R.	L.C. & Steel Tube
	Eng. Rm. & Aft.	one	.003	3	.036	4	28	O.R.	L.C. & Steel Tube
	WIRELESS								
	SEARCHLIGHT								
	MASTHEAD LIGHT								
	SIDE LIGHTS								
	COMPASS LIGHTS								
	POOP LIGHTS								
	CARGO LIGHTS								
	ARC LAMPS								
	HEATERS								

MOTOR CONDUCTORS.									
Ref. No.	DESCRIPTION.	No. of Motors.	Effective Area of each Conductor. Sq. Ins.	COMPOSITION OF STRAND.		Total Maximum Current. Amperes.	Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
				No.	Diameter.				
	BALLAST PUMP								
	MAIN BILGE LINE PUMPS								
	GENERAL SERVICE PUMP								
	EMERGENCY BILGE PUMP								
	SANITARY PUMP								
	CIRC. SEA WATER PUMPS								
	CIRC. FRESH WATER PUMPS								
	AIR COMPRESSOR								
	FRESH WATER PUMP								
	ENGINE TURNING GEAR								
	ENGINE REVERSING GEAR								
	LUBRICATING OIL PUMPS								
	OIL FUEL TRANSFER PUMP								
	WINDLASS								
	WINCHES, FORWARD								
	WINCHES, AFT								
	STEERING GEAR								
	(a) MOTOR GENERATOR								
	(b) MAIN MOTOR								
	WORKSHOP MOTOR								
	VENTILATING FANS								



All Conductors are of annealed copper conforming to British Standard Specification No. 7.

The Insulated Conductors are guaranteed to withstand the immersion and resistance tests specified in the Rules.

The foregoing is a correct description.

TELFORD, GRIER & MACKAY, LTD. Electrical Engineers.

Date 18-10-29

#### COMPASSES.

Distance between electric generators or motors and standard compass 60 feet

Distance between electric generators or motors and steering compass 60 feet

The nearest cables to the compasses are as follows:—

A cable carrying 3 Amperes 8 feet from standard compass 8 feet from steering compass.

A cable carrying 1/2 Amperes one foot from standard compass one foot from steering compass.

A cable carrying Amperes feet from standard compass feet from steering compass.

Have the compasses been adjusted with and without the electric installation at work at full power yes

Has the effect of switching on and off circuits, motors and other electro-magnetic apparatus within the vicinity of the compasses been noted yes

The maximum deviation due to electric currents was found to be nil degrees on any course in the case of the standard compass, and nil degrees on any course in the case of the steering compass.

Geo Brown & Co

Builder's Signature.

Date 21-10-29

Is this installation a duplicate of a previous case

No.

If so, state name of vessel

General Remarks (State quality of workmanship, opinions as to class, &c.)

This installation has been fitted on board under special survey. Tested under full load conditions and found satisfactory. The materials and workmanship were found to be good and sound.

It is submitted that this vessel is eligible for THE RECORD. Elec. Light.

31/10/29

Total Capacity of Generators

3.

Kilowatts.

The amount of Fee ...

£ 5.00

When applied for,

at 4/6

Travelling Expenses (if any) £

0.6

When received,

7-11-29

Committee's Minute

GLASGOW

29 OCT 1929

Assigned

Elec. Light



© 2021

Lloyd's Register Foundation