

Rpt. 11b.

B.T. COPY

Index No. **25403.**  
(For London Office only.)

# Lloyd's Register of Shipping.

## SURVEYS FOR FREEBOARD.—STEAM SHIPS.

PARTICULARS RELATING TO ALL STEAM SHIPS EITHER FLUSH DECKED, OR WITH TOP GALLANT FORECASTLES, SHORT POOPS AND BRIDGE HOUSES DISCONNECTED, OR WITH TOP GALLANT FORECASTLES HAVING LONG POOPS, OR RAISED QUARTER DECKS CONNECTED WITH BRIDGE HOUSES, OR OTHERWISE.

Port of Survey Manchester.  
Date of Survey 13+14-7-33.  
Name of Surveyor G. Anderson.

Ship's Name. <b>"CSARDA."</b>	Port of Registry and Nationality. <u>Budapest</u> <u>Hungarian.</u>	Official Number.	Gross Tonnage. <u>3872</u>	Date of Build. <u>1917</u>	Particulars of Classification. <u>+100 A.1.</u>
Number in Register Book					

Registered dimensions from Ship's Register.	LENGTH.	BREADTH.	DEPTH.	UNDER DECK TONNAGE.
	<u>360.1</u>	<u>50.0</u>	<u>22.95</u>	<u>3486.23</u>
Length on LOADLINE.	<u>360</u>	Frame Depth <sup>10</sup> / <sub>Rule</sub> <u>52</u> <u>2 x 42</u> <u>- 75</u> <u>Spring fitted</u>	Ceiling <u>+ 20</u> Sheer <u>+ 1.09</u> Tank Drop <u>4" + 16</u>	Peak Tanks <u>included</u>
CORRECTED DIMENSIONS.	<u>360</u>	<u>49.25</u>	<u>24.40</u>	<u>3486.23</u>

Co-efficient of fineness..... 8058Any modification necessary } CD 13.  
[Para. 4 (a) to (e)]\*Co-efficient as corrected ..... 78

Sheer { Stem..... 9'-6" } 14'-3" ÷ 2 = 85.5" ...Mean 47.55 = 85.45  
at { Sternpost ... 4'-9" }

Sheer at  $\frac{1}{2}$  of the length from { Stem 62 3/4" } 94 ÷ 2 = 47 ...Mean  
{ Sternpost 31 1/4" }  
85.5 + 15.45

Gradual mean Sheer ..... 85.45Standard mean Sheer [Table, Para. 18] ..... 46.00 Correction  
Difference..... 39.45 ÷ 4 = -9 3/4"

If limited as Para. 18 (f) .....

Rise in Sheer { At front of bridge house.....  
from amidships } ✓  
[Para. 18 (e)] { At after end of forecastle .....

Fall in Sheer } ÷ 2 = ✓  
Para. 18 (d) }

Length uncovered ..... Correction

## ALLOWANCE FOR DECK ERECTIONS:—

Freeboard, Table C..... 2'-9 1/4"  
Correction for Length, if required (Para. 12, 13, and 14) .... + 3 3/4"  
3'-1"  
Freeboard by Table A, corrected for sheer, and for length, }  
if required (Para. 11, 12, 13, and 14) } 5'-6 1/4"  
Difference..... 2'-5 1/4"  
Percentage as below..... 32.1%

Correction for R. Q. Dk. if engine and boiler openings not covered by bridge house (Para. 11)

Allowance for Deck Erections ..... -9.36  
-9 1/4"

	Length.	Length allowed.	Height.
Forecastle.....	<u>33.0 + 2.5 overhang</u>	<u>35.5</u>	<u>7'-6"</u>
Bridge House.....	<u>110.4 + 1.0 overhang</u>	<u>111.22</u>	<u>7'-6"</u>
+ Raised Qr. Dk.....	<u>✓</u>	<u>✓</u>	<u>✓</u>
Poop.....	<u>33.33 + wings</u>	<u>34.19</u>	<u>7'-6"</u>
Total .....		<u>180.91</u>	
Length of Ship .....		<u>360</u>	
Corresponding percentage {		<u>÷ 502</u>	
(Para. 11, 12, 13, or 14) }		<u>32.1%</u>	

Moulded Depth as measured..... 25'-5"Addition for Keel below base line for draught record..... 2 1/2 inches.

NOTE.—If the depth is measured when vessel is afloat, the details of measurement should be reported.

## CORRECTION FOR LENGTH.

Length of Ship on Loadline..... 360.0  
Length in Table ..... 365.0  
Difference ..... 55.0  
Correction for 10ft., Table A. .... 1.3 Table C. 7  
× Difference divided by 10 ..... 7.15 (if required.) 3.85  
If  $\frac{1}{10}$ ths length covered divide by 2 + 7 1/4" + 3 3/4"

## CORRECTION FOR IRON DECK.

Proportion covered, if less than  $\frac{1}{10}$ ths length covered ..... 50%  
Thickness of usual wood deck, less stringer ..... 3 1/2" - 1 3/4"

## CORRECTION FOR ROUND OF BEAM.

Breadth at Gunwale amidships..... 48'-10"  
Round of Beam ..... 12"  
Normal round..... 12 1/4"  
Difference ..... ÷ 2 =  
Proportion of Deck uncovered (Para. 19) ..... ✓

NOTE.—The round of beam should be reported on the full breadth of vessel at the gunwale.

Freeboard, Table A ..... 5'-8 3/4"  
Correction for Sheer ..... - 9 3/4"  
4'-11"  
Correction for Length ..... + 7 1/4"  
5'-6 1/4"  
Allowance for Deck Erections ..... - 9 1/4"  
4'-9"  
Correction for Round of Beam..... ✓  
Correction for fall in Sheer (if any)..... ✓  
Correction for Steel Deck (if required) ..... - 1 3/4"  
4'-7 1/4"  
Additions for non-compliance with provisions of } ✓  
Para. 11 (d) and (e) }  
Other Corrections (if any) ..... ✓

Winter Freeboard ..... 4'-7 1/4"  
Summer Freeboard ..... 4'-3"  
Indian Summer Freeboard ..... 3'-10 3/4"  
N. A. Winter Freeboard ..... ✓

Correction necessary because clearside amidships, measured in accordance with the Statute is not taken at the intersection of the wood or steel deck with side. N.L.

Winter Freeboard from deck line .....  
Summer " " " .....  
Indian Summer " " " .....  
N. A. Winter " " " .....  
25.7.33

## SUMMER FREEBOARD amidships from Centre of Disc to top of Deck Line, Wood, Steel, Deck:—

Tropical Fresh Water Line above Centre of Disc ... 9 1/2" = 242  
Fresh Water Line " " ... 5 1/2" = 140  
Tropical Line " " ... 4" = 102  
Winter Line below " " ... 4 1/2" = 114  
Winter North Atlantic Line " " ... ✓

Tropical Fresh Water Freeboard ... 3'-5 1/4" = 1047  
Fresh Water " " ... 3'-9 1/4" = 1149  
Tropical " " ... 3'-10 3/4" = 1187  
Winter " " ... 4'-7 1/4" = 1403  
Winter North Atlantic " " ... ✓

28 JUL 1933

RECEIVED 30 MAR 1936

RECEIVED 5 FEB