


s.s. " LEO "

It is submitted the Hull Surveyors be informed that the proposal to reinforce the hatch webs and deepening them by fitting a plate $15\frac{1}{2} \times \frac{1}{2}$ and transferring the existing angles to the bottom of this plate if these angles are still efficient, as indicated in the Builders' proposal No.1 on the accompanying sketch, could be approved provided the work be carried out to the satisfaction of the Surveyors.

The wood fore and afters at present fitted could be accepted but the bearing surface for these should be increased in width to 3".



10.8.32.

Plan to be returned to Surveyors who should again return it to this Office when forwarding verification of marking form.



© 2019

Lloyd's Register
Foundation

W40-0166