



(LLOYDS REGISTER.)

G. R. 130
Lloyds Register.

VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyds Register of British and Foreign Shipping.

Signal Letters (if any) J. N. W. T.

Official Number. 137260	Name of Ship. "Southwick"	No., Date, and Port of Registry. 1917. Sunderland.
No., Date, and Port of Previous Registry (if any).		
Whether British or Foreign Built. British	Whether a Sailing or Steam Ship; and if a Steam Ship how propelled. Steam Screw	Where Built. Sunderland
When Built. 1917		Name and Address of Builders. Swan, Hunter & Wigham Richardson Ltd. Southwick, Sunderland.
Number of Decks ... One	Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post ... 150	Feet. Tenth.
Number of Masts ... One	Length at quarter of depth from top of weather deck at side amidships to bottom of keel ... 149	4
Rigged ... Cutter	Main breadth to outside of plank ... 26	1
Stern ... Elliptical	Depth in hold from tonnage deck to ceiling at midships ... 10	75
Build ... Clincher	Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards ... 12	25
Galleries ... None	Depth from top of beam amidships to top of keel ... 11	81
Head ... None	Round of beam ... 32	54
Framework and description of vessel ... Steel	Length of engine room, if any ... 2	
Number of Bulkheads ... Three		
Number of water ballast tanks, and their capacity in tons ... One 5.68 tons		

PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel ... **731** Tons. Ditto per inch immersion at same depth ... **7.41** Tons.

PARTICULARS OF PROPELLING ENGINES, &c. (if any).

No. of sets of Engines.	Description of Engines.	Whether British or Foreign made.	When made.	Name and address of makers.	Reciprocating Engines. No. and Diameter of Cylinders in each set.	Length of Stroke.	Rotary Engines. No. of Cylinders in each set.	N. H. P. I. H. P. Speed of Ship.
One	Triple expansion Surface condensing	Engines.	Engines.	Engines.	Three	11"	21"	60
No. of Shafts.	Particulars of Boilers.	Boilers.	Boilers.	Boilers.	11"	14 1/2"	21"	350
One	Description: Byl. Multi. Number: One Iron or Steel: Steel Loaded Pressure: 100 lbs.	British	1917	Day Summers & Co. Southampton Palmer's S. & S. Co. Wexham	28"			8 1/2 knots


PARTICULARS OF TONNAGE.

GROSS TONNAGE.	No of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck ...	317.02	On account of space required for propelling power	162.58
Space or spaces between Decks...		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew	
Turret or Trunk ...	19.94	These spaces are the following, viz.:—	
Forecastle ...		Officers, Engineers & Crew	31.19
Bridge space ...	48.37	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:—	
Peep or Break ...	19.57	Cubic Metres Master's Accommodation 5.86	
Side Houses ...		Boatwain's Store 4.32	
Deck Houses ...	15.93	Water Ballast Space 20.93	31.11
Chart House ...	21.96	Total ...	224.88
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894 ...	442.79		
Excess of Hatchways ...	1253.10		
Gross Tonnage ...	224.88		
Deductions, as per Contra ...	217.91		
Registered Tonnage ...	616.69		

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is **46.97** tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is **16.60** tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

nil



Name of Master	Certificate of { Service No. Competency No.
No. of Owners	
Name, Residence, and Description of Managing Owner if there are more owners than one. Anglo-American Oil Company Limited, of 36, Queen Anne's Gate in the City of Westminster. Sixty-four Shares. James Hamilton of 36, Queen Anne's Gate, Westminster, S. W. designated manager.	
Dated 28th February, 1917.	