

REPORT ON ELECTRIC FITTINGS.

(OTHER THAN FOR THE PROPULSION OF THE VESSEL) 21 OCT 1933

Received at London Office

Date of writing Report 19 When handed in at Local Office 20 OCT 1933 Port of Hull

No. in Survey held at Hull. Date, First Survey 27.9.33 Last Survey 5.10. 1933

Reg. Book. 17720 on the Steam Trawler "ARAB" Tons { Gross 422. Net 162.

Built at Beverley By whom built Cook, Winton & Fenwick Ltd Yard No. 548 When built 1933

Owners Kelly & Son. Ltd Port belonging to Hull

Electric Light Installation fitted by Wm. Brandy & Sons. Ltd Contract No. When fitted 1933

Is the Vessel fitted for carrying Petroleum in bulk No

RETAIN

System of Distribution Two wire Pressure of supply for Lighting 100 volts, Heating ✓ volts, Power ✓

Direct or Alternating Current, Lighting Direct current Power ✓

If alternating current system, state frequency of periods per second

Has the Automatic Governor been tested and found efficient when the whole load is suddenly thrown on or off Yes

Generators, do they comply with the requirements regarding rating Yes, are they compound wound Yes

are they over compounded 5 per cent. Yes, if not compound wound state distance between each generator

Where more than one generator is fitted are they arranged to run in parallel ✓, is an adjustable regulating resistance fitted in series with each shunt field Yes

Are all terminals accessible, clearly marked, and furnished with sockets Yes, are they so spaced or shielded that they cannot be accidentally earthed, short circuited, or touched Yes

Are the lubricating arrangements of the generators as per Rule Yes

Position of Generators Starboard side of engine room, is the ventilation in way of the generators satisfactory Yes, are they clear of all inflammable material Yes

if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the generators

and ✓, are the generators protected from mechanical injury and damage from water, steam or oil Yes

are their axes of rotation fore and aft Yes

Earthing, are the bedplates and frames of the generating plant efficiently earthed Yes, are the prime movers and their respective generators in metallic contact Yes. Direct coupled

Main Switch Boards, where placed Beside generator in engine room

If the generators and main switchboard are not placed in the same compartment, is each generator provided with a fuse on each insulated pole as near as possible to the terminals of the generator, additional to that provided on the main switchboard ✓

Switchboards, are they placed in accessible positions, free from inflammable gases and acid fumes Yes

are they protected from mechanical injury and damage from water, steam or oil Yes, if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the switchboards ✓ and ✓

are they constructed wholly of durable, non-ignitable non-absorbent materials Yes, is all insulation of high dielectric strength and of permanently high insulation resistance Yes

if semi-insulating material is used, are all conducting parts insulated from the slab with mica or micanite or other non-hygroscopic insulating material, and the slab similarly insulated from its framework ✓

and is the frame effectively earthed Yes

Are the fittings as per Rule regarding: — spacing or shielding of live parts

Yes, accessibility of all parts Yes, absence of fuses on back of board Yes, proportion of omnibus bars

Yes, individual fuses to voltmeter, pilot or earth lamp Yes, connections of switches Yes

Main Switchgear, description of switchgear for each generator and each outgoing circuit, and arrangement of equalizer switches D.P. linked with

for generator. Outgoing circuits controlled by D.P. switches, and protected by fuses on each pole.

Instruments on main switchboard One ammeters. One voltmeters ✓ synchronising device for paralleling purposes.

Earth Testing, state what means are provided at the main switchboard for indicating the state of the insulation of the system

South lamps, with separate switches

Switches, Circuit Breakers and Fusible Cut-outs, do these comply with the requirements of the Rules Yes

Joint Boxes Section and Distribution Boards, is the construction, protection, insulation, material, and position of these as per rule Yes.

W414-0049 1/2
b400-714M

Cables: Single, twin, concentric, or multicore Twin are the cables insulated and protected as per Tables IV or V of the Rules Yes

Fall of Pressure, state maximum between bus bars and any point of the installation under maximum load 1 Volt.

Cable Sockets and other connections, are the ends of all cables having a sectional area of 0.04 square inch and above provided with soldering sockets Yes.

Paper Insulated Cables. If cables are paper covered, is the dielectric at the exposed ends of the conductor protected from moisture by being suitably sealed with insulating compound None

Cable Runs, are the cables fixed as far as possible in accessible positions not exposed to drip or accumulation of water or oil, or to high temperature from boilers, steam pipes, uptakes or other hot objects, or to avoidable risk of mechanical damage Yes.

Support and Protection of Cables, state how the cables are supported and protected Armoured cables with G.I. clips. L.C. cables with brass clips.

If cables are run in wood casings, are the casings and caps secured by screws Yes, are the cap screws of brass Yes, are the cables run in separate grooves Yes. If armoured and lead covered cables are secured by metal clips, are the clips spaced as per Table VIII Yes

Refrigerated Chambers, if lights are fitted, are the cables and fittings in accordance with the special requirements None

Joints in Cables, state if any, and how made, insulated, and protected None

Watertight Glands and Deck Tubes, are all cables passing through decks and watertight bulkheads provided with deck tubes or watertight glands Yes

Bushes in Beams and Non-watertight Partitions, where unarmoured cables pass through beams and non-watertight partitions, are the holes efficiently bushed Yes state the material of which the bushes are made Lead

Earthing Connections, state what earthing connections are fitted and their respective sectional areas Each lamp.

are their connections made as per Rule Yes

Alternative Lighting, are the groups of lights in the propelling machinery space arranged as per Rule Yes


Emergency Supply, state position and method of control of the emergency supply and how the generator is driven None

Navigation Lamps, are these separately wired Yes, controlled by separate switch and separate fuses Yes, are the fuses double pole Yes, are the switches and fuses grouped in a position accessible only to the officers on watch Yes, has each navigation lamp an automatic indicator as per Rule Yes

Secondary Batteries, are they constructed and fitted as per Rule Yes

Fittings, are all fittings on weather decks, in stokeholds and engine rooms and wherever exposed to drip or condensed moisture, watertight Yes, are any fittings placed in spaces in which goods are liable to be stacked in close proximity to them; if so, how are they protected None

are any fittings placed in spaces where inflammable or explosive dust or gases are liable to be present, if so, how are they protected None

where are the controlling switches situated 

Searchlight Lamps, No. of 1, whether fixed or portable Yes, are their fittings as per Rule Yes

Are Lamps, other than searchlight lamps, No. of 1, are their live parts insulated from the frame or case Yes, are their fittings as per Rule Yes

Motors, are their working parts readily accessible Yes, are the coils self-contained and readily removable for replacement Yes, are the brushes, brush holders, terminals and lubricating arrangements as per Rule Yes, are the motors placed in well-ventilated compartments in which inflammable gases cannot accumulate and clear of all inflammable material Yes, are they protected from mechanical injury and damage from water, steam or oil Yes, are their axes of rotation fore and aft Yes, if situated near unprotected woodwork or other combustible material, are the motors of the totally enclosed, pipe ventilated, forced draught, drip or flame proof type Yes, if not of this type, state distance of the combustible material horizontally or vertically above the motors Yes and Yes

Control Gear and Resistances, are the generator field and motor speed regulators, starters and controllers constructed and fitted as per Rule Yes

Lighting Conductors, where lightning conductors are required, are these fitted as per Rule Yes

Ships carrying Oil having a Flash Point less than 150° F. Have the special requirements of the Rules been complied with regarding switches, joint boxes, section and distribution boards, protection of cables, method of distribution, lead of cables, lights and fittings Yes

If portable lamps for use in dangerous spaces are supplied, are they of a type approved by the Home Office Yes

PARTICULARS OF GENERATING PLANT.

| DESCRIPTION OF GENERATOR. | No. of | RATED AT | | | | DRIVEN BY | WHERE DRIVEN BY AN INTERNAL COMBUSTION ENGINE. | |
|---------------------------|--------|------------|--------|-------|----------------|--------------|--|----------------------|
| | | Kilowatts. | Volts. | Amps. | Revs. per Min. | | Fuel Used. | Flash Point of Fuel. |
| MAIN | one | 6 | 100 | 60 | 350 | Steam Engine | | |
| AUXILIARY | | | | | | | | |
| EMERGENCY | | | | | | | | |
| ROTARY TRANSFORMER | | | | | | | | |

GENERATOR, LIGHTING AND HEATING CONDUCTORS.

| DESCRIPTION. | CONDUCTORS. | | COMPOSITION OF STRAND. | | TOTAL MAXIMUM CURRENT. AMPERES. | | Approximate Length. (Lead and Return.) Feet. | Insulated with | HOW PROTECTED. |
|------------------------|---------------|--|------------------------|-----------|---------------------------------|-------|--|----------------|----------------|
| | No. per Pole. | Total Effective Area per Pole Sq. Ins. | No. | Diameter. | In Circuit. | Rule. | | | |
| MAIN GENERATOR | 1 | 0.06 | 19 | 16.04 | 60 | | | V.I.R. | |
| EQUALISE CONNECTIONS | | | | | | | | | |
| AUXILIARY GENERATOR | | | | | | | | | |
| EMERGENCY GENERATOR | | | | | | | | | |
| ROTARY TRANSFORMER | | | | | | | | | |
| MOTOR GENERATOR | | | | | | | | | |
| ENGINE ROOM | 1 | 0.029 | 3 | 20.04 | 3.5 | 12 | 20 | " | L.C. Armoured |
| BOILER ROOM | 1 | | | | 1.5 | 12 | 40 | " | " |
| AUXILIARY SWITCHBOARDS | | | | | | | | | |
| ACCOMODATION | 1 | 0.2214 | 7 | 16.04 | 12 | 46 | 150 | " | " |
| Navigation Main | 1 | 0.07 | 7 | 20.04 | 6 | 24 | 150 | " | " |
| WIRELESS | 1 | 0.01 | 7 | 20.04 | 10 | 31 | " | " | " |
| SEARCHLIGHT | | | | | | | | | |
| MASTHEAD LIGHT | 1 | 0.029 | 3 | 20.04 | 2 | 12 | 150 | " | " |
| SIDE LIGHTS | 1 | | | | | | 30 | " | L.C. |
| COMPASS LIGHTS | | | | | | | | | |
| POOP LIGHTS | 1 | 0.045 | 7 | 22.04 | 5 | 18 | 150 | " | L.C. Armoured |
| CARGO LIGHTS | | | | | | | | | |
| ARC LAMPS | | | | | | | | | |
| HEATERS | | | | | | | | | |

MOTOR CONDUCTORS.

| DESCRIPTION. | No. of Motors. | CONDUCTORS. | | COMPOSITION OF STRAND. | | TOTAL MAXIMUM CURRENT. AMPERES. | | Approximate Length. (Lead and Return.) Feet. | Insulated with | HOW PROTECTED. |
|-------------------------|----------------|---------------|--|------------------------|-----------|---------------------------------|-------|--|----------------|----------------|
| | | No. Per Pole. | Total Effective Area per Pole Sq. Ins. | No. | Diameter. | In Circuit. | Rule. | | | |
| BALLAST PUMP | | | | | | | | | | |
| MAIN BILGE LINE PUMPS | | | | | | | | | | |
| GENERAL SERVICE PUMP | | | | | | | | | | |
| EMERGENCY BILGE PUMP | | | | | | | | | | |
| SANITARY PUMP | | | | | | | | | | |
| CIRC. SEA WATER PUMPS | | | | | | | | | | |
| CIRC. FRESH WATER PUMPS | | | | | | | | | | |
| AIR COMPRESSOR | | | | | | | | | | |
| FRESH WATER PUMP | | | | | | | | | | |
| ENGINE TURNING GEAR | | | | | | | | | | |
| ENGINE REVERSING GEAR | | | | | | | | | | |
| LUBRICATING OIL PUMPS | | | | | | | | | | |
| OIL FUEL TRANSFER PUMP | | | | | | | | | | |
| WINDLASS | | | | | | | | | | |
| WINCHES, FORWARD | | | | | | | | | | |
| WINCHES, AFT | | | | | | | | | | |
| STEERING GEAR | | | | | | | | | | |
| (a) MOTOR GENERATOR | | | | | | | | | | |
| (b) MAIN MOTOR | | | | | | | | | | |
| WORKSHOP MOTOR | | | | | | | | | | |
| VENTILATING FANS | | | | | | | | | | |

RETAIN

RETAIN

W414-0049 2/2

All Conductors are of annealed copper conforming to British Standard Specification No. 7.
 The Insulated Conductors are guaranteed to withstand the immersion and resistance tests specified in the Rules.
 The foregoing is a correct description.

WM BROADY & SON
 ENGLISH STREET
 HULL.

Electrical Engineers. Date 10 Oct. 1933

COMPASSES.

Distance between electric generators or motors and standard compass 75 feet
 Distance between electric generators or motors and steering compass
 The nearest cables to the compasses are as follows:—
 A cable carrying 5 Ampères 7 feet from standard compass 7 feet from steering compass.
 A cable carrying Ampères feet from standard compass feet from steering compass.
 A cable carrying Ampères feet from standard compass feet from steering compass.
 Have the compasses been adjusted with and without the electric installation at work at full power Yes
 Has the effect of switching on and off circuits, motors and other electro-magnetic apparatus within the vicinity of the compasses been noted Yes
 The maximum deviation due to electric currents was found to be no degrees on any course in the case of the standard compass, and no degrees on any course in the case of the steering compass.

WELTON & SEMMELL LTD

A. Clamper

Builder's Signature. Date 19-10-33

Is this installation a duplicate of a previous case Yes If so, state name of vessel "Cape Warwick" (for wiring)

General Remarks (State quality of workmanship, opinions as to class, &c.)

This vessel's electrical installation has been fitted on board under special survey & the materials & workmanship are good. It has been tried under full working conditions, found in good order, and is signed in my opinion to have record of Electric Light.

It is submitted that this vessel is eligible for elec. light

[Signature] 24/10/33

Total Capacity of Generators 6 Kilowatts.

The amount of Fee ... £ 4 : 0 : { When applied for, 17.10.33
 Travelling Expenses (if any) £ : : { When received, 11.11.33 W

[Signature]
 Surveyor to Lloyd's Register of Shipping.

Committee's Minute

Elec. Lt.

Assigned

Im. 1238.—Transfer.
 (The Surveyors are requested not to write on or below the space for Committee's Minute.)