

Amended

FREEBOARD REPORT on the

85 "Hamsterley"

It is submitted the Freeboards given on the accompanying

form, being those required by the Tables, merit approval, subject to

- 1) the air pipes on the poop, bridge and forecastle decks, 7" in height and under, being provided with non-detachable screwed plugs, or, alternatively, being renewed & made 18" in height to the openings, and efficient means of closing being provided for the openings of all air pipes if this is not already the case;
- 2) gangways, lifelines or other satisfactory means for the protection of the crew being provided in the after well, and in the forward well if the crew are berthed in the forecastle;
- 3) the 16" ventilator coaming 40" in height on the forecastle deck being efficiently supported.

Convention

Accepted
 Owners & Nac
 24/5/32.

LONDON.



© 2019

87.B.

24.5.32

David's Register
 Foundation

W45 0129

5 3/4"
 2
 3/4
 1/4
 1/2

3 1/2
 0 1/2
 9 1/2
 5 1/2

1/4

17