

COPY.

*Hullgate*  
Lloyd's Register of Shipping.



*Hullgate*

Port of Düsseldorf

17th June, 1936.

Order: G.3913/R.1395.

This is to Certify that

Heinrich Röhre

the undersigned Surveyor to this Society did at the request of

Messrs. Press-u. Walzwerk A.G. of Düsseldorf-Reisholz test and inspect on the 6th June 1936 at their work the undermentioned lapwelded Siemens-Martin Steel air receiver, manufactured in accordance with the approved plan No. G.O. 244 - date of approval 21.7.1932 - ordered by Messrs. Humboldt-Deutzmotoren A.G. of Köln - Deutz, and destined for Messrs. Clelands (Successors) Ltd. of Newcastle-on-Tyne and for the vessel No. 35.

Specification.

No. of rec.	Outs. diam.	Thickn. of shell	Thickn. of end plate	Length of rec.
1	474mm	12mm	55mm	3340mm

Results of tests.

Sample No.	Tensile str. in kg.p.sq.mm	Elongation in 8 inches
Shell plate 1	39,8	28,0%
" " 3	40,9	25,0%
" " 6	39,1	27,0%
End plates 126	41,7	38,0% in 2 inches

Bend tests satisfactory.

Hydraulic test: 60 Atm.  
Working pressure not to exceed: 30 Atm.  
For identification the receiver has been stamped:

No. 328  
LLOYDS TEST  
60 Atm.  
W.P. 30 Atm.  
H.R. 6.6.36.


*H. Röhre*

SURVEYOR TO LLOYD'S REGISTER

Fees: RM 10,-  
Expenses: RM 1,-  
Total: RM 11,-

Düsseldorf account No. 9192  
This Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that:—

"While the Committees of the Society use their best endeavours to ensure that the functions of the Society are properly executed, it is to be understood that neither the Society nor any Member of any of its Committees is under any circumstances whatever to be held responsible for any inaccuracy in any report or certificate issued by the Society or its Surveyors, or in any entry in the Register Book or other publication of the Society, or for any error of judgment, default or negligence of any of its Committees or any Member thereof, or the Surveyors, or other Officers or Agents of the Society."



Lloyd's Register  
Foundation

W 415 - 0177