

Particulars for Freeboard.

No. *10.* Name *Town Screw Steamer.*

Registered Length *410.5'*

" Breadth *52.6'*

" Depth to tank *24.7'*

" Tonnage, under deck Gross

Length on load line *409.6"*

Depth moulded *27' 3" To UPPER 35' 3" To SHELTER.*

Camber of weather deck *1' 1"*

Length of weather deck beam *51.9'*

Rule thickness of wood deck *4"*

Sheer deck at side forward at perpendicular through L. line (in ins.) *28'*

" " " " aft " " " *55'*

" " " 8th. L. on L.L. from perpendicular forward *54'*

" " " " " aft *30'*

Length of forecastle (actual on deck) *34' 0"* Height *8' 0"*

Overhand of forecastle deck abaft bulkhead *28' 0"*

Length of bridge on deck *183'* Height *8' 0"*

Overhang of bridge deck beyond forward bulkhead *10' 0"*

" " " " aft " *15' 0"*

Length of poop on deck from aft perpendicular *26' 0"* Height *8' 0"*

Overhang of poop deck beyond bulkhead *6' 0"*

Bulkhead at aft end of forecastle *Steel*

" " fore end of bridge *Steel*

Stiffening to forward bridge bulkhead *To Rule.*

Bulkhead at fore end of poop *Steel*

Size and number of freeing ports *To Rule.*


Height of hatch coamings above deck *2' 6"* Covers *3"*

Sizes of hatches 1. *17' x 12'* 2. *25' 6" x 14' 3.25' x 14' 4.* 5.

Scuppers *To Rule.*


Height of lowest side scuttle above base *26' 0"*

Builders letter states Load draft about 24'



Lloyd's Register
Foundation
W416 0072

Referred to the O



© 2021

Lloyd's Register
Foundation