

dimensions from
Ship's Register

GRAPHIC ADDRESS—
EDWELL, ABERDEEN."

CONTRACTORS TO THE ADMIRALTY.

of Strikes, Lock-outs, Break-
Machinery, Accidents, Stress
ther, or other causes beyond
trol, we cannot hold ourselves
for failure to deliver by the
ecified.

OFFICE TELEPHONE, 1269.
W. G. JAMESON—TELEPHONE No. 2421.
JOHN FIDDES—TELEPHONE No. 1773.

W. G. JAMESON.
JOHN FIDDES.
E. M. DUTHIE.

TORRY,

ABERDEEN,

26th. March, 1920.

THE JOHN DUTHIE TORRY SHIPBUILDING CO.

Lloyds Surveyors,

Regent Quay,

Aberdeen.

Dear Sirs,

S.S. Nos. 459/60.

The Owners instruct us to ask for provisional freeboards
for these vessels, with the poop bridge and foxle off the tonnage and
also with these on the tonnage.

The particulars are as follows:-

Length on load line.....	227.5'	✓
breadth extreme.....	34.1'	✓
Frame depth 6".....	Cargo battens 2".....	✓
Depth moulded 16.0'.....	Round up .75'	✓
Double bottom.....	2.75'	✓
Depth in hold to top of tank.....	14.0'	✓
Ceiling (in way of hatches only).....	2½"	✓
Under deck tonnage (approximately).....	850 tons.	✓
Co-efficient of fineness.....	.74	
Correction for D.B.....	.02	
Modified co-efficient.....	.72	
Sheer at stem.....	.83"	81
" 1/8 from stem.....	41½"	✓
" at post.....	44½"	✓
" 1/8 from port.....	23"	✓
" at front of bridge.....	4"	✓
" at end of foxle.....	21½"	✓
Foxle (tonnage openings).....	51 x 7.5'	✓
Bridge and poop (tonnage openings).....	142' x 7.5'	✓
Upper bridge.....	15' x 8'	✓
Casing.....	41' x 7'	✓

Further particulars will be found on plans in your possession.

Yours faithfully,

NOTE—Please address reply to the firm and not to individual partners to insure prompt attention.

W416-0149

© 2021
Lloyd's Register
Foundation

Ship

not
whole
12, 13, 0