

# REPORT ON ELECTRIC FITTINGS.

(OTHER THAN FOR THE PROPULSION OF THE VESSEL)

4 SEP 1930

Date of writing Report 19... When handed in at Local Office 3. 9. 1930 Port of Newcastle-on-Tyne

No. in Survey held at Newcastle Date, First Survey 21<sup>st</sup> July Last Survey 30 July 1930  
Reg. Book. Supp. S. S. Holmside. (Number of Visits 3)

93809 on the S. S. Holmside. Tons { Gross Net

Built at Newcastle By whom built Cowpen DDOs + SBC Ltd Yard No. 248 When built 1930

Owners Burnett S. S. Co Ltd Port belonging to Newcastle

Electric Light Installation fitted by Sunderland Forge & Eng Co Ltd Contract No. 248. When fitted 1930

Is the Vessel fitted for carrying Petroleum in bulk No

System of Distribution DOUBLE WIRE

Pressure of supply for Lighting 110 volts, Heating - volts, Power - volts.

Direct or Alternating Current, Lighting DIRECT Power

If alternating current system, state frequency of periods per second -

Has the Automatic Governor been tested and found efficient when the whole load is suddenly thrown on or off YES

Generators, do they comply with the requirements regarding rating YES, are they compound wound YES

are they over compounded 5 per cent. YES, if not compound wound state distance between each generator

Where more than one generator is fitted are they arranged to run in parallel YES, is an adjustable regulating resistance fitted in series with each shunt field YES

Are all terminals accessible, clearly marked, and furnished with sockets YES, are they so spaced or shielded that they cannot be accidentally earthed, short circuited, or touched YES

Are the lubricating arrangements of the generators as per Rule YES

Position of Generators ENGINE ROOM

is the ventilation in way of the generators satisfactory YES, are they clear of all inflammable material YES

if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the generators

and YES, are the generators protected from mechanical injury and damage from water, steam or oil YES

are their axes of rotation fore and aft YES

Earthing, are the bedplates and frames of the generating plant efficiently earthed YES, are the prime movers and their respective generators in metallic contact YES

Main Switch Boards, where placed ENGINE ROOM

If the generators and main switchboard are not placed in the same compartment, is each generator provided with a fuse on each insulated pole as near as possible to the terminals of the generator, additional to that provided on the main switchboard

Switchboards, are they placed in accessible positions, free from inflammable gases and acid fumes YES

are they protected from mechanical injury and damage from water, steam or oil YES, if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the switchboards

are they constructed wholly of durable, non-ignitable non-absorbent materials YES, is all insulation of high dielectric strength and of permanently high insulation resistance YES

if semi-insulating material is used, are all conducting parts insulated from the slab with mica or micaite or other non-hygroscopic insulating material, and the slab similarly insulated from its framework YES

and is the frame effectively earthed YES. Are the fittings as per Rule regarding:— spacing or shielding of live parts YES

accessibility of all parts YES, absence of fuses on back of board YES, proportion of omnibus bars YES

individual fuses to voltmeter, pilot or earth lamp YES, connections of switches YES

Main Switchgear, description of switchgear for each generator and each outgoing circuit, and arrangement of equalizer switches

D.P. SWITCH AND P. HANDLE-TYPE FUSES FOR GENERATOR. S.P. SWITCHES AND P. FUSES FOR EACH CIRCUIT


Instruments on main switchboard 1 ammeters 1 voltmeters - synchronising device for paralleling purposes.

Earth Testing, state what means are provided at the main switchboard for indicating the state of the insulation of the system

LAMPS CONNECTED THRO SWITCH & FUSE ON EACH POLE TO EARTH

Switches, Circuit Breakers and Fusible Cut-outs, do these comply with the requirements of the Rules YES

Joint Boxes Section and Distribution Boards, is the construction, protection, insulation, material, and position of these as per rule YES



**Cables:** Single, twin, concentric, or multicore SINGLE are the cables insulated and protected as per Tables IV or V of the Rules YES.

**Fall of Pressure,** state maximum between bus bars and any point of the installation under maximum load 5.0 V.D.

**Cable Sockets and other connections,** are the ends of all cables having a sectional area of 0.04 square inch and above provided with soldering sockets YES.

**Paper Insulated Cables.** If cables are paper covered, is the dielectric at the exposed ends of the conductor protected from moisture by being suitably sealed with insulating compound -

**Cable Runs,** are the cables fixed as far as possible in accessible positions not exposed to drip or accumulation of water or oil, or to high temperature from boilers, steam pipes, uptakes or other hot objects, or to avoidable risk of mechanical damage YES.

**Support and Protection of Cables,** state how the cables are supported and protected VULCANISED INDIA-RUBBER IN PIPE. RUN IN HOLDS  
TWEEN DECKS. ACCOMMODATION. ETC.

If cables are run in wood casings, are the casings and caps secured by screws YES, are the cap screws of brass YES, are the cables run in separate grooves YES. If armoured and lead covered cables are secured by metal clips, are the clips spaced as per Table VIII -

**Refrigerated Chambers,** if lights are fitted, are the cables and fittings in accordance with the special requirements -

**Joints in Cables,** state if any, and how made, insulated, and protected NONE

**Watertight Glands and Deck Tubes,** are all cables passing through decks and watertight bulkheads provided with deck tubes or watertight glands YES

**Bushes in Beams and Non-watertight Partitions,** where unarmoured cables pass through beams and non-watertight partitions, are the holes efficiently bushed YES, state the material of which the bushes are made LEAD & FIBRE

**Earthing Connections,** state what earthing connections are fitted and their respective sectional areas -  
are their connections made as per Rule -

**Alternative Lighting,** are the groups of lights in the propelling machinery space arranged as per Rule YES

**Emergency Supply,** state position and method of control of the emergency supply and how the generator is driven NONE

**Navigation Lamps,** are these separately wired YES, controlled by separate switch and separate fuses YES, are the fuses double pole YES, are the switches and fuses grouped in a position accessible only to the officers on watch YES, has each navigation lamp an automatic indicator as per Rule YES

**Secondary Batteries,** are they constructed and fitted as per Rule NONE

**Fittings,** are all fittings on weather decks, in stokeholds and engine rooms and wherever exposed to drip or condensed moisture, watertight YES, are any fittings placed in spaces in which goods are liable to be stacked in close proximity to them; if so, how are they protected -, are any fittings placed in spaces where inflammable or explosive dust or gases are liable to be present, if so, how are they protected -, how are the cables led -, where are the controlling switches situated -

**Searchlight Lamps, No. of** -, whether fixed or portable -, are their fittings as per Rule -

**Arc Lamps,** other than searchlight lamps, No. of -, are their live parts insulated from the frame or case -, are their fittings as per Rule -

**Motors,** are their working parts readily accessible -, are the coils self-contained and readily removable for replacement -, are the brushes, brush holders, terminals and lubricating arrangements as per Rule -, are the motors placed in well-ventilated compartments in which inflammable gases cannot accumulate and clear of all inflammable material -, are they protected from mechanical injury and damage from water, steam or oil -, are their axes of rotation fore and aft -, if situated near unprotected woodwork or other combustible material, are the motors of the totally enclosed, pipe ventilated, forced draught, drip or flame proof type -, if not of this type, state distance of the combustible material horizontally or vertically above the motors - and -

**Control Gear and Resistances,** are the generator field and motor speed regulators, starters and controllers constructed and fitted as per Rule -

**Lightning Conductors,** where lightning conductors are required, are these fitted as per Rule YES

**Ships carrying Oil having a Flash Point less than 150° F.** Have the special requirements of the Rules been complied with regarding switches, joint boxes, section and distribution boards, protection of cables, method of distribution, lead of cables, lights and fittings -

If portable lamps for use in dangerous spaces are supplied, are they of a type approved by the Home Office -

PARTICULARS OF GENERATING PLANT.

DESCRIPTION OF GENERATOR	No. of	RATED AT				DRIVEN BY	WHERE DRIVEN BY AN INTERNAL COMBUSTION ENGINE	
		Kilowatts.	Volts.	Amps.	Revs. per Min.		Fuel Used.	Flash Point of Fuel.
MAIN	1	8	110	72.7	380	STANDARD OPEN TYPE S.F.M.E. CO.		
AUXILIARY						STEAM ENGINE.		
EMERGENCY								
ROTARY TRANSFORMER								

GENERATOR, LIGHTING AND HEATING CONDUCTORS.

DESCRIPTION.	CONDUCTORS.		COMPOSITION OF STRAND.		TOTAL MAXIMUM CURRENT. AMPERES.		Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
	No. per Pole.	Total Effective Area per Pole Sq. Ins.	No.	Diameter.	In Circuit.	Rule.			
MAIN GENERATOR	1	.06	19	.064	72.7	85	45	RUBBER	LEAKS.
EQUALISER CONNECTIONS									
AUXILIARY GENERATOR									
EMERGENCY GENERATOR									
ROTARY TRANSFORMER MOTOR GENERATOR									
ENGINE ROOM	1	.003	3	.036	6.13	12	45	"	"
BOILER ROOM									
AUXILIARY SWITCHBOARDS									
ENGINE & ARC ROOM	1	.0145	7	.052	18.5	37	90	"	BRAIDED IN PIPE.
NAVIGATION	1	.002	3	.029	2.8	7.8	300	"	"
ACCOMMODATION SALOON & FORWARD	1	.0145	7	.052	20	37	300	"	"
WIRELESS	1	.007	7	.036		24	240	"	"
SEARCHLIGHT									
MASTHEAD LIGHT									
SIDE LIGHTS									
COMPASS LIGHTS									
POOP LIGHTS									
CARGO LIGHTS									
ARC LAMPS									
HEATERS									

MOTOR CONDUCTORS.

DESCRIPTION.	No. of Motors.	CONDUCTORS.		COMPOSITION OF STRAND.		TOTAL MAXIMUM CURRENT. AMPERES.		Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
		No. per Pole.	Total Effective Area per Pole Sq. Ins.	No.	Diameter.	In Circuit.	Rule.			
BALLAST PUMP										
MAIN BILGE LINE PUMPS										
GENERAL SERVICE PUMP										
EMERGENCY BILGE PUMP										
SANITARY PUMP										
CIRC. SEA WATER PUMPS										
CIRC. FRESH WATER PUMPS										
AIR COMPRESSOR										
FRESH WATER PUMP										
ENGINE TURNING GEAR										
ENGINE REVERSING GEAR										
LUBRICATING OIL PUMPS										
OIL FUEL TRANSFER PUMP										
WINDLASS										
WINCHES, FORWARD										
WINCHES, AFT										
STEERING GEAR										
(a) MOTOR GENERATOR										
(b) MAIN MOTOR										
WORKSHOP MOTOR										
VENTILATING FANS										

All Conductors are of annealed copper conforming to British Standard Specification No. 7.  
 The Insulated Conductors are guaranteed to withstand the immersion and resistance tests specified in the Rules.  
 The foregoing is a correct description.

I, PRO THE SCOTLAND FORGE & ENGINEERING CO., LTD.

*Thos. Thompson*

Electrical Engineers.

Date 26 AUG 1930

COMPASSES.

Distance between electric generators or motors and standard compass 94 FEET.

Distance between electric generators or motors and steering compass 98 FEET.

The nearest cables to the compasses are as follows:—

A cable carrying 2.8 Ampères 8 feet from standard compass 6 feet from steering compass.

A cable carrying Ampères feet from standard compass feet from steering compass.

A cable carrying Ampères feet from standard compass feet from steering compass.

Have the compasses been adjusted with and without the electric installation at work at full power *Yes*.

Has the effect of switching on and off circuits, motors and other electro-magnetic apparatus within the vicinity of the compasses been noted *Yes*.

The maximum deviation due to electric currents was found to be *Nil* degrees on *any* course in the case of the standard

compass, and *Nil* degrees on *any* course in the case of the steering compass.

For and on behalf of  
 SCOTLAND DRY DOCK & SHIPBUILDING CO., LTD.

*Thos. Thompson*  
 General Manager.

Builder's Signature.

Date 29. 8. 30.

Is this installation a duplicate of a previous case *No*. If so, state name of vessel *✓*

General Remarks (State quality of workmanship, opinions as to class, &c.)

*This installation has been fitted on board under special survey. Tested under full working conditions and found satisfactory. The materials and workmanship were found to be good and sound.*

It is submitted that  
 this vessel is eligible for  
 THE RECORD. Elec. Light.

*(Signature)*  
 10/9/30.

Total Capacity of Generators 8 Kilowatts.

The amount of Fee ... £ 8.0.0 : { When applied for, 5.8.30  
 Travelling Expenses (if any) £ : : { When received, 29.8.30 *SAT*

*J. Rankin for W. T. Badger.*  
 Surveyor to Lloyd's Register of Shipping.

Committee's Minute

Assigned *Elec. Light*

Im. 1228.—Transfer.  
 (The Surveyors are requested not to write on or below the space for Committee's Minute.)

