

MIDSHIP SECTION.

SCALE 1:25.

PASSENGER AND CARGO MOTORSHIP TO CLASS LLOYD'S REG. 100A I ✚

COMPLETE SUPERSTRUCTURE VESSEL WITH FREEBOARD. FIXED DRAFT 8.685 m. (28'-6")

DIMENSIONS: 142.30 · 19.51 · 12.2 METRES. (466'-8" · 64'-0" · 40'-0").

LENGTH OF CRUISER STEAM 6.50 + 141.73 = 148.23 · 96% = 142.40 METRES.

## SCANTLING NUMERALS

$$\begin{aligned} L \cdot D & 142.30 \cdot 12.2 = 1736 \\ L \cdot (B \cdot D) & 142.30 \cdot (19.51 + 12.2) = 4512 \\ \frac{L}{D} & \frac{142.30}{12.2} = 11.66 \\ d & 9.450 \div 1.200 = 8.250 \end{aligned}$$
EQUIPMENT NUMERALS:

2 <sup>ND</sup> NUMERALS L. (B+D) =	4512
BRIDGE AN FORECASTLE =	210
DECKHOUSES =	183
	4905

EQUIPMENTS:

2 OFF STOCKLESS ANCHOR EACH 4500 KG COL WEIGHT 13080 KG.  
1 " " " 3940 -  
1 " STEAM ANCHOR 1345 - EXCL STOCK 25% MAX STOCK  
550 M 6 1/2" STUD CHAIN CABLES MIN WEIGHT 52580 KG  
280 M 12 7/8" STEEL WIRE FOR STEAM ANCHORS 6 x 24 SPECIAL FLEXIBLE  
240 M 140% " " TOWLINE 6 x 24 " "  
4 OFF 135 M 20 3/4" MANILLA HANDSaws AND WIPERS  
OK 70% STEEL WIRE 6 x 12 FLEXIBLE.

APPROVED ELECTRODES TO BE USED WHERE  
ELECTRIC WELDING EMPLOYED OWNERS  
CONSENT OBTAINED.

W420-0050



M/V "Canada"

Midship Section

A/ S Nakshov. Skipsværft. N<sup>o</sup> 62

"as built"

RETAIN



© 2019

Lloyd's Register  
Foundation

W420

-00SD