

FREEBOARD REPORT on the *S. S. Wm 14/15. Cantiere ed Officine
Meridionale, Baia.*

It is submitted the Genoa surveyors be informed that before the builders enquiries can be answered it will be necessary for them to forward full particulars on form 116. They should be informed that for freeboard purposes D deck is the weather deck and they should report full particulars of the erections on this deck, observing that the spaces in way of the ship's side openings are considered to be open wells. In view of the proposal to leave the ends of the bridges open, all openings in such spaces which provide communication with the spaces below D deck should be fitted with battening arrangements. The surveyors should report particulars of such openings. The sketch forwarded by the surveyors should be returned to them and they should fill in particulars of openings, doorways, etc. and return it to this office with their freeboard report.

Ar. 15776

W.D.

15.2.26

Lloyd's Register
Foundation

W423-0129