

CSS Ship
(Standard Tween Decks)

31480

Index No. _____
(For London Office only.)

Lloyd's Register of Shipping.

SURVEYS FOR FREEBOARD.

PARTICULARS IN RESPECT OF STEAM SHIPS HAVING SPAR-OR
AWNING DECKS.

Port of Survey _____

Date of Survey *20-7-25*

Name of Surveyor _____

Ship's Name. Number in Register Book	Port of Registry and Nationality.	Official Number.	Gross Tonnage.	Date of Build.	Particulars of Classification.
<i>Canterio 20 Officiu meridionali</i> <i>Baia 40. No 14175</i>					

Registered dimensions from Ship's Register.	LENGTH. <i>485.57</i>	BREADTH. <i>61.68</i>	DEPTH.	UNDER DECK Tonnage.
Length on LOADLINE		Frame Depth Rule "	Ceiling Sheer	Peak Tanks
CORRECTED DIMENSIONS.				

Co-efficient of fineness

Any modification necessary
[Para. 4 (a) to (e)*]

Co-efficient as corrected

(Given) *.70*

Allowance for strength in excess of Lloyd's rules =

State particulars—

Moulded Depth *assumed* *36'-3 1/2"* Main Deck.
" " *as given* *44'-3 1/2"* Spar or Awning Deck.

Assuming standard
'tween-deck height.

Addition for Keel below base line for
draught record.....inches.NOTE.—If the
depth is measured
when vessel is
afloat, the details
of measurement
should be reported.

CORRECTION FOR LENGTH:—

Length of Ship on Load Line..... *485.57*
Length in Table *435.50*
Difference..... *50.07*
Correction for 10ft..... *.8*
× Difference ÷ 10 = *4.0* *+4"*

Height of 'Tween Decks..... *8'-0"*
(From top of beam to top of beam at side)
Correction for Height of 'Tween Decks in Spar-decked Ships.....

Freeboard Table *B or C* *(9-8 1/2-3-1)* *6'-7 1/2"*
Correction for Length..... *+ 4"*
6'-11 1/2"

Correction for Strength in excess of Lloyd's rules.....

Correction for Iron Deck if required..... *- 3 1/2"*
Other Corrections (if any)..... *6'-8"*

Winter Freeboard..... *6'-8"*
Summer Freeboard..... *7 1/2"* *6'-0 1/2"*
Indian Summer Freeboard.....
N. A. Winter Freeboard.....

Correction necessary because clearside amidships measured
in accordance with the Statute is not taken at inter-
section of the wood or steel deck with side

Winter Freeboard from Deck Line *36'-4"*
Summer " " *6'-0 1/2"*
Indian Summer " " *30'-3 1/2"*
N.A. Winter " "

Summer M.L.

FREEBOARD recommended amidships from centre of Disc to top of Statutory Deck Line, Wood (Steel) Deck:—

Fresh Water Line	above centre of Disc
Indian Summer Line	"	"	"
Winter Line	below	"	"
Winter North Atlantic Line	"	"	"

NOTE.—All vessels equal in strength to Lloyd's Spar-decked rule, or which, although in excess of that rule, do not come up to Lloyd's requirements for Ships of full
scantlings to the upper deck, are to be considered as Spar-decked Ships, the freeboard for which will vary with their strength.
All vessels equal in strength to Lloyd's Awning-decked rule, or which, although in excess of that rule, do not come up to Lloyd's requirements for a Spar-
decked Vessel, are to be considered as Awning-decked Ships, the freeboard for which will vary with their strength.
* If the frames, skin planking, or ceiling are of unusual thickness the breadth of vessel to inside of ceiling should be reported if possible.