

Equivalent depth for 27' 0"  
Mld depth

31480

Index No. \_\_\_\_\_  
(For London Office only.)

# Lloyd's Register of Shipping.

## SURVEYS FOR FREEBOARD.

(3)

PARTICULARS IN RESPECT OF STEAM SHIPS HAVING SPAR OR AWNING DECKS.

Port of Survey \_\_\_\_\_  
Date of Survey 20-7-21  
Name of Surveyor \_\_\_\_\_

Ship's Name. antieri ed Officin Meridionali  
Baia No. 14-15  
Number in Register Book \_\_\_\_\_  
Port of Registry and Nationality. \_\_\_\_\_  
Official Number. \_\_\_\_\_  
Gross Tonnage. \_\_\_\_\_  
Date of Build. \_\_\_\_\_  
Particulars of Classification. \_\_\_\_\_

Registered dimensions from Ship's Register.	LENGTH.	BREADTH.	DEPTH.	UNDER DECK Tonnage.
	485.57	61.68		
Length on LOADLINE		Frame Depth Rule	Ceiling Sheer	Peak Tanks
CORRECTED DIMENSIONS.				

Moulded Depth as measured ..... 31'-8 1/2" Main Deck.  
" " " ..... Spar or Awning Deck.

Addition for Keel below base line for draught record.....inches.

NOTE.—If the depth is measured when vessel is afloat, the details of measurement should be reported.

Co-efficient of fineness .....  
Any modification necessary [Para. 4 (a) to (e)] }  
Co-efficient as corrected .....

(Given) .70

CORRECTION FOR LENGTH:—

Length of Ship on Load Line.....	485.57
Length in Table.....	380.50
Difference.....	105.07
Correction for 10ft.....	8
× Difference ÷ 10 =	8.4 ✓

+ 8 1/2"

Allowance for strength in excess of Lloyd's rules =

State particulars—

Height of 'Tween Decks.....  
(From top of beam to top of beam at side)  
Correction for Height of 'Tween Decks in Spar-decked Ships.....

Freeboard Table B or C .....	4' - 10 1/2" ✓
Correction for Length.....	+ 8 1/2" ✓
Correction for Height of 'Tween Decks in Spar-decked Ships.....	5' - 7" ✓

Correction for Strength in excess of Lloyd's rules.....

Correction for Iron Deck if required.....	- 3 1/2" ✓
Other Corrections (if any).....	5' - 3 1/2" ✓

Winter Freeboard.....	5' - 3 1/2" ✓
Summer Freeboard.....	6 1/2" ✓
Indian Summer Freeboard.....	4' - 9" ✓
N.A. Winter Freeboard.....	

Correction necessary because clearside amidships measured in accordance with the Statute is not taken at inter-section of the wood or steel deck with side

Winter Freeboard from Deck Line .....	
Summer " " " .....	31' - 9" ✓
Indian Summer " " " .....	4' - 9" ✓
N.A. Winter " " " .....	27' - 0 1/2" ✓


Summer Mld

FREEBOARD recommended amidships from centre of Disc to top of Statutory Deck Line, Wood (Steel) Deck:—

Fresh Water Line	above centre of Disc	...	...	...	...	...	...	...	...
Indian Summer Line	" " "	...	...	...	...	...	...	...	...
Winter Line	below	" " "	...	...	...	...	...	...	...
Winter North Atlantic Line	" " "	...	...	...	...	...	...	...	...

NOTE.—All vessels equal in strength to Lloyd's Spar-decked rule, or which, although in excess of that rule, do not come up to Lloyd's requirements for Ships of full scantlings to the upper deck, are to be considered as Spar-decked Ships, the freeboard for which will vary with their strength. All vessels equal in strength to Lloyd's Awning-decked rule, or which, although in excess of that rule, do not come up to Lloyd's requirements for a Spar-decked Vessel, are to be considered as Awning-decked Ships, the freeboard for which will vary with their strength.

\* If the frames, skin planking, or ceiling are of unusual thickness the breadth of vessel to inside of ceiling should be reported if possible.



© 2019

Lloyd's Register  
Foundation  
W423-0135