

FREEBOARD REPORT on the s.s. " LOWLAND "

It is submitted the Freeboards given on the accompanying form, being those required by the Tables, merit approval.

subject to:-


1. The fidley grating steel covers being permanently attached by hinges.
2. Efficient means of closing being provided for all air pipes and ventilators.
3. The freeing port area on each side of the raised quarter deck being increased to 15 sq. ft.
4. The width of the hatch cover bearing surface of the forward hold and bunker hatchways on the fidley top being increased to $2\frac{1}{2}$ ", and one additional tarpaulin being provided for the fore peak hatchway on the fore castle deck, for each of the trimming hatchways on the bridge deck and for the bunker hatchway on the fidley top.

It is further submitted the freeboard certificate and copies be sent to the Surveyors with the assignment letter for issue when the above conditions of assignment have been complied with, and the freeboard marks on the ship's sides verified.

5. 9. 32.

CONVENTION.

Also to Owners & Hull



© 2020

Lloyd's Register
Foundation

W428-0087