

FREEBOARD PARTICULARS.

Name Noord Holland

Class when below 100A

Description of Vessel 110⁺

Table A No. of page 50

Moulded Depth 14 Feet 3 Inches.

Coefficient of Fineness -72

Feet. Inches.

NORMAL FREEBOARD BY TABLES (WINTER) ... 2 - 2 3/4

	Additions. Inches.	Deductions. Inches.
Sheer		<u>5 3/4</u>
Length... ..	<u>2 1/4</u>	
Erections		<u>8 3/4</u>
Height between Decks		
Round of Beam		
Iron Deck		<u>3</u>
Class being below 100A		
Statutory Deck Line	<u>1 1/4</u>	
Other Special Circumstances		
Summer Difference		<u>2</u>
TOTALS	<u>3 1/2</u>	<u>19 1/2</u>
Let Increase or Decrease		<u>16</u>

SUMMER FREEBOARD ...

1 - 4

0 - 10 1/2

W428-0097

If the frames, skin planking, or ceiling are of unusual character, the character of the material and the method of construction should be reported if possible.
In vessels obtaining an allowance for deck erections under Para. 11 where the sheer drops abaft amidships the height of the R.Q.D. is to be taken from the level of the top of the amidship beam.
In flush-decked vessels the total standard mean sheer means the sheer measured at the stem and stern.