

Josephine Charlotte

Antwerp.
Belgian

3422

1929/4

+ 100

Number in Register Book

LENGTH

BREADTH

DEPTH

UNDER DECK

s.s. "JOSEPHINE CHARLOTTE".

IT IS SUBMITTED the Freeboards given on the accompanying form, being those required by the Tables, merit approval, subject to:-

1. Hatch covers, tarpaulins and efficient battening arrangements being fitted to the bunker hatchways in the bridge tween decks.
2. The storm covers on the fidley gratings being permanently secured in position, if this is not already the case.
3. Efficient means of closing being provided for all air pipes.
4. The scuppers from the bridge space to the bilges in the pocket bunkers being permanently closed by riveted plates.
5. Gangways, lifelines or other satisfactory means of protection for the crew being fitted in the forward and after wells.

The freeboards under the Convention being greater than the existing freeboards, the latter have been re-assigned.

IT IS FURTHER SUBMITTED a copy of the report and assignment letter be sent to Mr. Herbert for confirmation of the assignment by the Belgian Authorities. Mr. Herbert should inform this Office when approval is obtained.

Belgian Convention.

7. 6. 32.

STB

Assg. by owners & Ant
8/6/32.



© 2019

Lloyd's Register
Foundation

W435-0221

Tropical Line

Winter Line

below

... 4.5 ... = 114

... 4.0 ... = 102

Tropical

Winter

JUN 1932