

Lloyd's Register of Shipping.

SURVEYS FOR FREEBOARD-STEAM SHIPS.

PARTICULARS RELATING TO ALL STEAM SHIPS EITHER FLUSH DECKED, OR WITH TOP GALLANT FORECASTLES, SHORT POOPS AND BRIDGE HOUSES DISCONNECTED, OR WITH TOP GALLANT FORECASTLES HAVING LONG POOPS, OR RAISED QUARTER DECKS CONNECTED WITH BRIDGE HOUSES, OR OTHERWISE.

Port of Survey Rotterdam
Date of Survey Building
Name of Surveyor P. J. R. van den Burg

Ship's Name S. S. Christiansborg Port of Registry Copenhagen Official Number 483 Gross Tonnage 331.73 Date of Build. 1925 Particulars of Classification 100 A1
Number in Register Book 1932.86 Contemplated

Registered dimensions from ship's Register. LENGTH. 332.2 BREADTH. 48.7 DEPTH. 22.2 UNDER DECK TONNAGE. 2924.43

Length on LOADLINE. 332 Frame Depth 10 Ceiling 10 Peak 1 } incl. Rule 5 1/2 Sheer +1.2 Tanks 1

CORRECTED DIMENSIONS. 332 47.95 23.41 2924.43

Co-efficient of fineness..... .78
Any modification necessary { [Para. 4 (a) to (e)]* 6.8.8
Co-efficient as corrected76

Sheer { Stem..... 9' 9 1/2" 176.75 ÷ 2 = 88.37 Mean at { Sternpost 4' 11 1/4"

Sheer at 1/3 of the length from { Stem 5' 4 1/2" 95.5 ÷ 2 = 47.75 Mean { Sternpost 2' 4"

Gradual mean Sheer 86.81

Standard mean Sheer [Table, Para. 18] 48.20 Correction

Difference..... 48.61 ÷ 4 = - 11

§ If limited as Para. 18 (f) - 11

Rise in Sheer { At front of bridge house..... 4' 2 3/8" from amidships { At after end of forecastle 6' 11 3/4" [Para. 18 (e)]

¶ Fall in Sheer { Para. 18 (d) } 1 ÷ 2 = 0.5
Length uncovered ✓ Correction

ALLOWANCE FOR DECK ERECTIONS:—

Freeboard, Table C..... 2-5 1/2
Correction for Length, if required (Para. 12, 13, and 14)

Freeboard by Table A, corrected for sheer, and for length, if required (Para. 12, 13, and 14) 4-5

Difference 1-11 1/2

Percentage as below..... 61%

Correction for R. Q. Dk. if engine and boiler openings not covered by bridge house (Para. 11) }

Allowance for Deck Erections 14 1/2

	Length.	Length allowed.	Height.
Forecastle.....	<u>24.2</u>	<u>3.0</u>	<u>4' 6"</u>
Bridge House	<u>212.3</u>	<u>27.2</u>	<u>4' 6"</u>
† Raised Qr. Dk.....		<u>212.3</u>	
Poop.....	<u>30.1</u>	<u>30.1</u>	<u>4' 6"</u>
Total		<u>269.6</u>	
Length of Ship		<u>332</u>	<u>= .81</u>

Corresponding percentage { (Para. 41, 12, 13, or 14) 61%

FREEBOARD recommended amidships from centre of Disc to top of Statutory Deck Line, Wood (Iron) Deck:—

	Fresh Water Line	above centre of Disc
Indian Summer Line	"	"
Winter Line	below	"
Winter North Atlantic Line	"	"

¶ If the frames, skin planking, or ceiling are of unusual thickness the breadth of vessel to inside of ceiling should be reported if possible.
† Vessels obtaining an allowance for deck erections under Para. 11 where the sheer drops about amidships the height of the R.Q.D. is to be taken from the level of the top of the amidship beam.
§ In flush-decked vessels the total standard mean sheer means the sheer measured at the stem and sternpost. In vessels having poops and forecastles, it means the sheer measured at points distant one-eighth of the vessel's length from stem and sternpost.

Moulded Depth as measured..... 24' 6"

Addition for Keel below base line for draught record... 1 1/2 inches.

NOTE.—If the depth is measured when vessel is afloat, the details of measurement should be reported.

CORRECTION FOR LENGTH.

Length of Ship on Loadline..... 332'
Length in Table 294
Difference 38
Correction for 10ft., Table A. 1.3 Table C. ✓
× Difference divided by 10 4.94 (if required.)
If 1/10ths length covered divide by 2 2.47 + 2 1/2

CORRECTION FOR IRON DECK.

Proportion covered, if less than 1/10ths length covered
Thickness of usual wood deck, less stringer 3 1/2

CORRECTION FOR ROUND OF BEAM.

Breadth at Gunwale amidships..... 2
Round of Beam 12" over 48'
Normal round..... 12
Difference ÷ 2 =
Proportion of Deck uncovered (Para. 19)

NOTE.—The round of beam should be reported on the full breadth of vessel at the gunwale.

Freeboard, Table A	<u>5-4</u>
Correction for Sheer	<u>11</u>
Correction for Length	<u>4-5</u>
Allowance for Deck Erections	<u>1-2 1/2</u>
Correction for Round of Beam.....	<u>3-5 1/4</u>

Correction for fall in Sheer (if any).....	<u>- 3 1/2</u>
Correction for Iron Deck (if required)	<u>3-1 3/4</u>

Additions for non-compliance with provisions of { Para. 11 (d) and (e) } ✓
Other Corrections (if any) ✓

Winter Freeboard	<u>3-1 3/4</u>
Summer Freeboard	<u>2-9 1/2</u>
Indian Summer Freeboard	<u>2-5 1/4</u>
N. A. Winter Freeboard	<u>✓</u>

Correction necessary because clearside amidships, measured in accordance with the Statute is not taken at the intersection of the wood iron deck with side. 1 3/4

Winter Freeboard from deck line	<u>3-3 1/2</u>
Summer " " " "	<u>2-11 1/4</u>
Indian Summer " " " "	<u>2-7</u>
N. A. Winter " " " "	<u>✓</u>

Freeing port area on back of this form.	<u>2-11"</u>
State dimensions of freeing port area on back of this form.	<u>5 1/2</u>
	<u>4</u>
	<u>4 1/2</u>

† The Surveyor should state whether the fall in sheer as reported is measured relatively to the straight line of keel or to the water line. If measured relatively to water line the vessel's draft at time of survey, and also the usual load draft forward and aft, should be reported.

MARKING REPORT.
REVISED 30.1.22

W437-0074

Do all the Frames extend to the top height in the Poop? *Yes* Raised Quarter Deck? *Yes* Bridge House? *Yes* Forecastle? *Yes*
 To what height do the Reverse Frames extend? *2 frames*
 Has the Poop or Raised Quarter Deck an efficient Iron Bulkhead at the fore end? *Yes*
 Give particulars of the means for closing the openings in Bulkhead *No. Doors closed*
 Is the Poop or Raised Quarter Deck connected with the Bridge House? *No* Has the Bridge House an efficient Bulkhead at the fore end? *Yes*
 Give particulars of the means for closing the openings in Bulkhead *Two small hinged doors*
 What is the thickness of the Bridge Front plating? *38* and Coaming plate? *42*
 Give scantlings and spacing of the Stiffeners *L 240 x 90 x 13 1/2 spaced 30"*
 Are bracket plates fitted at each end of the Stiffeners? *Yes* Are hor'l. brackets fitted connecting Bridge Bulk'd. with Bulwarks? *Yes*
 Has the Bridge House an efficient Iron Bulkhead at the after end? *Yes*
 How are the openings closed? *Steel plates strong backs*
 Is the Forecastle at least as high as the main or top-gallant rail? *Yes* Has the Forecastle an efficient Iron or Wood Bulk'd. at after end? *Yes Steel*
 Are the Engine and Boiler openings covered by a Bridge, Poop, Raised Quarter Deck, or enclosed by a Strong Iron or Steel Deckhouse? *Bridge*
 If the openings are not so protected are the exposed parts of the Casings efficiently constructed? *Yes*
 Give thickness of plating; scantlings and spacing of Stiffeners *34/28 L 4 x 3 x .36 spaced 30"*
 What is the height of the exposed Casings? *4'9"* Are suitable means provided for closing all openings in them in bad weather? *Yes*
 Are the Weather Deck Hatchways efficiently constructed and at least equal to the requirements of Section 28 of Rules for 1904-5? Give particulars below *As below*

Are the Weather Deck Hatchways efficiently constructed and at least equal to the requirements of Section 28 of No. 1 and No. 5. Rules for 1901-5? Give particulars below. No. 2 and No. 3. <i>No below.</i> <i>No. 4.</i>											
Position and Size.		<i>26' 6 1/2" x 20' 0"</i>		<i>28' 7" x 20' 0"</i>		<i>22' 5 1/2" x 20' 0"</i>					
Item.		Ship.	Rule.	Ship.	Rule.	Ship.	Rule.	Ship.	Rule.	Ship.	Rule.
COAMING.	Height above top of DECK	<i>4' 0.</i>		<i>3' 0."</i>		<i>3' 0."</i>		<i>} as approved.</i>			
	Thickness {	Sides.....	<i>. 44</i>	<i>. 44.</i>		<i>. 44</i>					
		Ends.....	<i>. 44.</i>	<i>. 44.</i>		<i>. 44.</i>					
SHIFTING BEAMS OR WEB PLATES.	Number	<i>5 Webs in all Hatchways.</i>									
	Section and Scantlings	<i>JL- 17" x .36 L 4 x 3 x .44. for all Hatchways.</i>									
		Material									
* FORE AND AFTERS.	Number										
	Section and Scantlings										
		Material									
HATCHES Thickness		<i>3" Hatchways for all Hatchways.</i>									
Remarks.....											

* The depth of Fore and Afters should be stated from the underside of the hatches in all cases.

(If the sill of the lowest side scuttle will be less than 6 inches above the Indian Summer Load Line if assigned under the tables, state vertical distance from top of deck at side amidships to lower edge of lowest side scuttle.)

The following information is to be given in all Cases of vessels dealt with under Paras. 11, 12 (under 15 feet Moulded depth) and under Shelter Deck Rules.

What is the thickness of the Bridge Sheerstrake? Strake between Main and Bridge Sheerstrakes?

Delete the words { The Crew are, ~~are not~~, berthed in the bridge house. *Poops.*
 that do not apply { The arrangements to enable them to get backwards and forwards from their quarters are, ~~are not~~ satisfactory. *Langways.*

Length of Bulwarks in well *forward and aft. 32' 8"*

Area of Freeing Ports required by Para. 11 (e) each side of vessel = Sq. ft.

Ft. Tenth. Ft. Tenth. No. } Freeing Ports (each side of vessel) = Sq. ft.

Each well = 3.45

x 1.8 x 2.

Total deficiency or excess = Sq. ft.

The vessel has been built in accordance with the approved plan.

Sister vessel is S.S. Sierra Leone.

Prod No 481. Same Builders.

Show hereon line of Floors or Tank Top with position of any Breaks in same; also height of Peak Tank tops, &c., &c.

State any special features in the construction of the Vessel *Plans in London retained*

Builders. Jan Smid & Zn. Rotterdam.

See Letter. M. 14/2. 1920.

Owners *Lampskibsselskabet "Lønnebrog"*

Address *Copenhagen.*

Fee *108.00* will be received by me *P. Rasmussen*



© 2019

Lloyd's Register Foundation