

131.

FREEBOARD REPORT on the

Chevy Chase

It is submitted the Freeboards given on the accompanying form, being those required by the Tables, merit approval, subject to:—

- not prop
wd*
- ① ~~Airpipes on Bridge and Poop Decks being increased in height to 18 inches, and satisfactory means of closing being provided for all airpipes.~~
 - ② ~~Storm valve being fitted on ship side to galley discharge pipe.~~
 - ③ Lifelines or other satisfactory means being supplied on the trunks for the protection of the crew.
 - ④ Number 5 Double Bottom Tanks being adequately longitudinally subdivided.
 - ⑤ Strong angle or metal sockets, spaced not more than 10 feet apart, efficiently secured to the stringer plate, or equally efficient means being provided for securing the uprights.
 - ⑥ Eyeplates for securing the lashings being riveted to the sheerstrake at intervals of not more than 10 feet, the distance from an end bulkhead of a superstructure to the first eyeplate being not more than 6 feet 6 inches.
 - ⑦ Steering rods being efficiently protected against damage by deck cargo.

For Timber Deck Cargo

29% L. now divided

Convention and Timber

The Secretary.

LONDON.

Lloyd's Register
Foundation
12.4.32.

3-6½

3-2¾

2-11