

tered ns from Register.	LENGTH.	BREADTH.	DEPTH.	UNDER DECK TONNAGE.	Moulded Depth as measured.....
at after end?	231.0	30.9	12.0	576.85	

t from London Report No. 77915 of Survey for Repairs  
to the S.S. "CATO", June, 1915.

### Board Alterations.

Owners requesting freeboard survey, attended and found  
age opening fitted with 12" coaming, 3" covers over same, and  
ening down cleats and tarpaulins. Wash port in tween deck  
e aft closed in with riveted plate and scuppers discharging  
w tween deck overboard removed and riveted plates fitted  
ring holes in shell plating, the tween decks now draining to  
es.

Subsequently Owners withdrew freeboard application,  
ing it was not desired for the moment to have any deeper  
ing, as on completion of present charter, in all probability  
vessel would have the closed openings re-opened.



© 2020

Lloyd's Register  
Foundation

W439-0054

Raised Qr. Dk.....

op.....

Total

intersection of the wood or iron deck with