

Length of Ship on Loadline..... 470.00
 Length in Table 420.875

Name of Vessel *T.M.V. "SVEABORG"*

No. in Register Book.....

	FEET.	INCHES.
Moulded Depth	35	4
Stringer Plate		$\frac{3}{4}$
Thickness of wood sheathing if required		✓
Statutory deck line above intersection of <u>actual</u> deck at side		$1\frac{3}{4}$
Total depth from top of statutory deck line to top of keel	35	$6\frac{1}{2}$
Freeboard recorded	8	$7\frac{1}{2}$
Moulded Draft	26	11
Add for keel—Flat or Bar		$1\frac{3}{4}$
Draught	27	$0\frac{3}{4}$
Draught for record	Δ <i>27-0$\frac{3}{4}$</i>	

1m, 10, 20.

$$\Delta \text{ coeff at } .85 \text{ Dm} = \frac{20570 \times 35}{470.0 \times 64.25 \times 35.33 \times .85} = .794 \quad \checkmark$$

W439-0244

BOARD recommended amidships from centre of Disc to top of Statutory Deck Line, ~~Wood~~ (Steel) Deck :— ... $8\frac{1}{2}$... $8\frac{1}{2}$
 Fresh Water Line above centre of Disc ... $6\frac{1}{2}$... $6\frac{1}{2}$