

5m, 5.32.

## FREEBOARD REPORT on the

H/S GOWRIE

The  
beam  
report  
a full  
vessel  
rule.

It is submitted the Freeboards given on the accompanying form, being those required by the Tables, merit approval, Subject to:-

- ① The bearing surface of the hatch covers of No 1 and 2 hatchways being increased to  $2\frac{1}{2}$ " and all hatch beams, sockets and fore and afters being made efficient to the surveyor's satisfaction.
- ② The 6" diameter ventilators on the fore-castle deck which are cut flush with the deck, being permanently closed by metal plates or alternatively having efficient coverings fitted, and all ventilator coverings and air pipes being provided with efficient means of closing.
- ③ The plating port area on each side of the forward cell and raised quarter deck being increased to  $12\frac{1}{4}$  and  $16\frac{3}{4}$  square feet respectively.

Convention

Assd. Lk. Jnr  
G.D.M.  
8/7/32



W440-0331

© 2021

STB  
Lloyd's Register  
Foundation  
8-7-32

11 <sup>3</sup>/<sub>4</sub>