

Copy for the Malmö Office

Rpt. 6.

For the information of Surveyors and the Committee only.

Received at

Malmö

of date

20/10

10 273

Lloyd's Register of British & Foreign Shipping.

(Report on Vessel No.

597

Port

Malmö.)

No. 6009

SHIP ~~FORGINGS~~ OR CASTINGS.

I have to report that the undermentioned ~~Iron~~ Steel ~~Forgings~~ Castings, manufactured by the Surahammar Steel Works of Surahammar, Sweden, for the Vessel No. ~~138~~ 143 being built by Kockums Mek. Verkstads A.B. of Malmö, Sweden, have been inspected by me as set forth below and found to be, so far as can be seen, good, sound and free from defects.

Stockholm the 27th October 1923.

~~Forgings~~ Castings.

Lloyd's

No. 6009

1.26.10.23. A.



	STERN FRAME.	RUDDERxFRAME.	STEM.
1*	S. M. Steel.		
ade	Cast and annealed.		
ions	L = 14'- 10.3/8" x H = 23'- 11". Section 7.3/8" x 5 1/8"		
s on Inspection	Cast and annealed.		
hen Inspected	25 and 26 Oct. 1923.		
CASTINGS.			
on Standard Test Pieces.			
Test—			
per square inch 97144	43,6		
ension per cent. ...	37,3		
ending Test—			
le before fracture	120° Radius 1"		
est—			
ht from ground ...	10 feet.		
ering Test—			
ade according to Rules d found satisfactory ...	As per Rules, satisfactory.		

SKETCHES OF FRAMES SHOWING POSITION AND DESCRIPTION OF WELDS OF FORGINGS.

7 testholes have been drilled in the stern frame, in way of the pouring heads.

A. Bakson

Fee (if any chargeable) £

To be paid at

* If of Iron, state whether scrap or puddled Iron. If of steel, state whether made on the Open Hearth process.