

CLASS CONTEMPLATED.

(LLOYD'S REGISTER.)

G.R. 130.
Lloyd's Register.

VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of British and Foreign Shipping.
Signal Letters (if any) L.G.M.R.

Official Number.	Name of Ship.	No., Date, and Port of Registry.	
149,166.	Sea Venture.	2 in 1930 Dover.	
No., Date, and Port of Previous Registry (if any).			
Whether British or Foreign Built.	Whether a Sailing Steam, or Motor Ship, if Steam or Motor Ship how propelled.	Where Built.	Name and Address of Builders.
British	Steam Screw.	Sunderland.	Swan Hunter & Wigham, Richardson, Ltd., Sunderland.
Number of Decks ...	One	Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post ...	Feet. 294 Tenth. 1
Number of Masts ...	Two	Length at quarter of depth from top of weather deck at side amidships to bottom of keel ...	289 5.8
Rigged ...	Schooner	Main breadth to outside of plank ...	43 1.
Stern ...	Elliptical	Depth in hold from tonnage deck to ceiling at midships ...	18 8.
Build ...	Clincher	Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards ...	-- --
Galleries ...	None	Depth from top of beam amidships to top of keel ...	20 8.3
Head ...	None	Depth from top of deck at side amidships to bottom of keel ...	21 0.2
Framework and description of vessel ...	Steel Cargo	Round of beam ...	-- 8.5
Number of Bulkheads ...	Seven	Length of engine room, if any ...	42 0
Number of water ballast tanks, and their capacity in tons ...	Eight-753 tons.		

PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel ... 4,323 Tons. Ditto per inch immersion at same depth ... 25.09 Tons.

PARTICULARS OF PROPELLING ENGINES, &c. (if any).

No. of sets of Engines.	Description of Engines.	Whether British or Foreign made.	When made.	Name and address of makers.	Reciprocating Engines. No. and Diameter of Cylinders in each set.	Length of Stroke.	Rotary Engines. No. of Cylinders in each set.	N. H. P. I. H. P. Speed of Ship.
One	Reciprocating Tri-Compound Direct Acting Vertical.	Engines.	Engines.	Engines.	Three			206
		British	1930	North Eastern Marine Eng. Co., Ltd., Sunderland.	20 1/2"			1200
No. of Shafts.	Particulars of Boilers.	Boilers.	Boilers.	Boilers.	33"	36"		
One	Description ... Cyl. Mult. ... Number ... Two ... Iron or Steel ... Steel ... Loaded Pressure ... 180 lbs.	British	1930	North Eastern Marine Eng. Co., Ltd., Sunderland.	54"			10 1/2 knots

PARTICULARS OF TONNAGE.

GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck ...	1978.53	On account of space required for propelling power	744.55
Space or spaces between Decks...		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew	131.69
Turret or Trunk ...	6.22	These spaces are the following, viz.:- Poop, 3 Deck and 2 Side Houses (Number of Seamen or Apprentices for whom accommodation is certified... 31.....)	
Forecastle ... (Houses in)	24.00		
Bridge space (Store in)	76.30		
Poop or Break	31.52		
Side Houses	83.53		
Deck Houses	5.32		
Chart House		Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:-	
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894 ...	121.31	Masters Accommodation 7.77 Chart Space 5.32 Wireless Space 3.03 Boats Stores 12.38 Water Ballast Spaces 47.60	75.98
Excess of Hatchways ...	2326.73	Cubic Metres 6584.65	
Gross Tonnage ...	952.22	2694.79	
Deductions, as per Contra ...	1374.51	3889.86	
Register Tonnage ...		Total ...	952.22

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 343.21 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 82.78 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Forecastle	L. 24.9'	-	31.75 tons.
Bridge	L. 66.0'	-	124.35 tons.
Passages abreast casings	L. 28.5' X 2	-	15.16 tons.

Name of Master

Certificate of { Service No.
Competency No.

No. of Owners

Name, Residence, and Description of Managing Owner if there are more owners than one.

Dover Navigation Co., Ltd.,

196, London House, Crutched Friars, London, E.C.3.

Sixty-four Shares.

Charles Frederick Leach
of same address-Manager-

Dated at Dover, 17th September, 1930.