

Floyd's Register of Shipping.  
SURVEYS FOR FREEBOARD.—STEAM SHIPS.

PARTICULARS RELATING TO ALL STEAM SHIPS EITHER FLUSH DECKED, OR WITH TOP GALLANT FORECASTLES, SHORT POOPS AND BRIDGE HOUSES DISCONNECTED, OR WITH TOP GALLANT FORECASTLES HAVING LONG POOPS, OR RAISED QUARTER DECKS CONNECTED WITH BRIDGE HOUSES, OR OTHERWISE.

Port of Survey

Date of Survey

Name of Surveyor

Ship's Name.

SEA VENTURE.

Port of Registry  
and Nationality.Dover  
BritishOfficial  
Number.

149166

Gross  
Tonnage.

2327

Date of Build.

1930

Particulars of Classification.

+100 A.I.

Number in Register Book

Registered dimensions from Ship's Register.	LENGTH.	BREADTH.	DEPTH.	UNDER DECK TONNAGE.
	294.1	43.1	18.8	1978.53
Length on LOADLINE.	290.0	Frame Depth 8 Rule " 5 1/2 2 x 2 1/2 After Ceiling fitted	No. Ceiling + 20 Sheer + 97	Peak } Tanks } und.
ATED IONS.	290.0	42.68	19.97	1978.53

cient of fineness.....

80

modification necessary }

C.D.B.

ara. 4 (a) to (e)]\*

cient as corrected .....

78.

Stem.....	84	126 ÷ 2 = 63	Mean	73.86
Sternpost ...	42			36 3/4 86
at 1/8 of the length from	Stem 54 Sternpost 27.25	81.25 ÷ 2 =	40.62..Mean	73.86
al mean Sheer .....	73.86-63	68.43		97

ard mean Sheer [Table, Para. 18] .....	39.00	Correction
Difference.....	29.43	÷ 4 = 7.36

imited as Para. 18 (f) .....	- 7 1/4"
------------------------------	----------

in Sheer	At front of bridge house.....
amidships	At after end of forecastle .....

in Sheer	÷ 2 =
a. 18 (d) }	✓
h uncovered .....	Correction

## ALLOWANCE FOR DECK ERECTIONS :—

board, Table C.....	1-6 3/4
tion for Length, if required (Para. 12, 13, and 14) .....	+ 2 1/2
board by Table A, corrected for sheer, and for length, }	3-11 1/2
if required (Para. 11, 12, 13, and 14) .....	2-2 1/4
ence .....	25.45%
atage as below.....	

tion for R. Q. Dk. if engine and boiler openings not }	
covered by bridge house (Para. 11) .....	- 6 1/2"
ance for Deck Erections .....	

	Length.	Length allowed.	Height.
astle.....	23.37	23.37	7-6"
e House .....	66.0 + 2'6" overhang	67.87	7-6"
ed Qr. Dk.....			
	26.62	26.62	7-6"
Total .....		117.86	
h of Ship .....		290.00	4065.
ponding percentage }	25.45%		
ra. 11, 12, 13, and 14) }			

## SUMMER FREEBOARD amidships from Centre of Disc to top of Deck Line, Wood, Steel, Deck :—

Tropical Fresh Water Line above Centre of Disc ...	8"
Fresh Water Line .....	5"
Tropical Line .....	3"
Winter Line below .....	3"
Winter North Atlantic Line .....	5"

Tropical Fresh Water Freeboard ...	3'-0 1/4"
Fresh Water .....	2'-4 1/4"
Tropical .....	2'-7 1/4"
Winter .....	2'-9 1/4"
Winter North Atlantic .....	3'-5 1/4"

Moulded Depth as measured..... 20'-10"

Addition for Keel below base line  
for draught record..... 1 1/4" inches.NOTE.—If the  
depth is measured  
when vessel is  
adroit, the details  
of measurement  
should be reported.

## CORRECTION FOR LENGTH.

Length of Ship on Loadline.....	290
Length in Table .....	250
Difference .....	40
Correction for 10ft., Table A. ....	1.2
× Difference divided by 10 .....	4.8
If 1/10ths length covered divide by 2	+4 3/4"
Table C. ....	.6
(if required.)	2.4
	12 1/2"

## CORRECTION FOR IRON DECK.

Proportion covered, if less than 1/10ths length covered .....	4065
Thickness of usual wood deck, less stringer .....	3 1/2
	1.42 = - 1 1/2"

## CORRECTION FOR ROUND OF BEAM.

Breadth at Gunwale amidships.....	42.70
Round of Beam .....	10.25
Normal round.....	10.67
Difference .....	42" ÷ 2 = 21"
Proportion of Deck uncovered (Para. 19) .....	59.35
	NIL.

NOTE.—The  
round of beam  
should be report-  
ed on the full  
breadth of vessel  
at the gunwale.

Freeboard, Table A .....	4'-2"
Correction for Sheer .....	7 1/4"
Correction for Length .....	3'-6 3/4"
Allowance for Deck Erections .....	4 3/4"
Correction for Round of Beam.....	3'-11 1/2"
Correction for fall in Sheer (if any).....	6 3/4"
Correction for Steel Deck (if required) .....	3'-4 3/4"
Additions for non-compliance with provisions of }	
Para. 11 (d) and (e) ‡	-
Other Corrections (if any) .....	-

Winter Freeboard .....	3'-3 1/4"
Summer Freeboard (A=2 1/2" C=3 1/2")	3'-0 1/4"
Indian Summer Freeboard .....	2'-9 1/4"
N. A. Winter Freeboard .....	3'-5 1/4"

Correction necessary because clearside amidships, measured  
in accordance with the Statute is not taken at the  
intersection of the wood or steel deck with side.

NIL.

Winter Freeboard from deck line .....	
Summer " " " .....	
Indian Summer " " " .....	
N. A. Winter " " " .....	

SEP 1932

F.W. = 5002 / 40 x 25.48 = 4.91 = 5" MARKING FORM

13 MAY 1935

MARKING FORM

28 SEP 1932

MARKING FORM

RECEIVED

W443-0201