


Name of Vessel *Motor Vessel "Sliedrecht"*

No. in Register Book

	FEET.	INCHES.
Moulded Depth	28	0
Stringer Plate		1/2
Thickness of wood sheathing if required		-
Statutory deck line above intersection of <u>actual</u> deck at side		1 3/4
Total depth from top of statutory deck line to top of keel	28	2 1/4
Freeboard recorded	6	3
Moulded Draft	21	11 1/4
Add for keel—Flat or Bar		1 1/2
Draught	22	0 3/4
Draught for record		

A. Scale 22'-0 3/4"



© 2020

Lloyd's Register
Foundation

of ceiling should be reported if possible.
In vessels obtaining an allowance for deck erections under Para. 11 where the sheer drops abaft amidships the height of the R.Q.D. is to be taken from the level of the top of the amidship beam.
In flush-decked vessels the total standard mean sheer means the sheer measured at the stem and stern-post. In vessels having poops and forecastles, it means the sheer measured at points distant one-eighth of the vessel's length from stem and stern-post.

The Surveyor should state whether the fall in sheer as reported is measured line of keel or to the water line. If measured relatively to water line survey, and also the usual load draft forward and aft should be reported.

RETAIN



© 2020

Lloyd's Register
Foundation