

ss. Daghistan

FREEBOARD REPORT on the

NOTE—If the vessel is measured the details measurement be reported.

It is submitted the Freeboards given on the accompanying form, being those required by the Tables, merit approval, the same to be marked on the vessel's sides, inserted in the certificate of classification, and recorded in the Register Book, subject to

- ① two tarpaulins being fitted to all hatchways on the freeboard & poop decks other than those closed by steel covers.
- ② the steel hinged covers to the store hold & pump room gratings being repaired.
- ③ the air pipes on the freeboard deck being increased to 30" in height to the openings, & those on the hatchway covers being increased to 24" in height to the openings above the hatchway covers.
- ④ Efficient means of closing being provided for the openings of all air pipes.
- ⑤ deadlights being supplied for the side scuttles where missing.
- ⑥ life-lines being fitted forward of the saloon house for the protection of the crew.

Convention

The owners should be informed that ^{no increase} freeboard cannot be assigned in this case owing to the absence of a fore-castle.

ST. B. Lloyd's Register
9.4.32 W447-0045

covers to the three small hatchways on each side

11-4