

Lloyd's Register of Shipping.
SURVEYS FOR FREEBOARD.

PARTICULARS IN RESPECT OF STEAM SHIPS HAVING SPAR OR AWNING DECKS.						Port of Survey
						Date of Survey
						Name of Surveyor
<div>Complete Shelter Deck Without Tonnage Opening</div>						
Ship's Name.	Port of Registry and Nationality.	Official Number.	Gross Tonnage.	Date of Build.	Particulars of Classification.	
S. S. DAGHESTAN.	Newcastle British		5741.67	1921	100 A1. Shelter Deck With freeboard. Carrying Petroleum in cylindrical tanks	
Number in Register Book						
Registered dimensions from Ship's Register.	LENGTH.	BREADTH.	DEPTH.	UNDER DECK Tonnage.	Moulded Depth as measured	
	405.0	52.0	31.5	5524.93	26' 6" Main Deck.	
Length on LOADLINE	404.75	Frame Depth 4' 6 1/2 Rule " 6' 5 1/2 x 2 = - .20 no ceiling + 33	Ceiling + .20 Sheer + 1.15 Tank top level.	Peak } Tanks } Incl. ✓	34' 6" Shelter Spar or Awning Deck.	
CORRECTED DIMENSIONS.	404.75	52.13.	32.85.	5524.93.		
Co-efficient of fineness80 Any modification necessary [Para. 4 (a) to (e)] - .02 Cell. B. Bottom .78. Co-efficient as corrected76 to upper Deck.						Addition for Keel below base line for draught record.....inches.
Allowance for strength in excess of Lloyd's rules =						NOTE.—If the depth is measured when vessel is afloat, the details of measurement should be reported
State particulars— This vessel has complete steel shelter decks without tonnage opening & is built on the longitudinal system. The upper deck is of steel plated from trunk sides to ship's sides. The vessel is fitted with cylindrical tanks. There are 9 W.T. Bulkheads in the vessel, 4 of which nos 9, 13 1/2, 14 1/2 & 31 extend to the shelter deck & the remainder to the upper deck.						CORRECTION FOR LENGTH :— Length of Ship on Load Line.... 404.75 Length in Table 318 Difference..... 86.45 Correction for 10ft..... .7 x Difference ÷ 10 = + 6"
Gradual 91.81 50.44 36 41.34 1.15. Sheer at Stem 120 } at 1/2 length from Stem 64 } 50.5 Sternpost... 61 } 90.5 " " " Sternpost... 34 } Drop in Sheer abaft amidships.....						Height of 'Tween Decks..... 8' 0" (From top of beam to top of beam at side) Correction for Height of 'Tween Decks in Spar-decked Ships.....
Shelter Round of Spar-deck Beam..... 12 1/2. " " Main-deck " 13.						Freeboard Table B or C 3' 1" Correction for Length..... + 6" 3' 7" Correction for Height of 'Tween Decks in Spar-decked Ships..... 8' 0" 11' 4" Correction for Strength in excess of Lloyd's rules..... 2' 4 1/2" 8' 11 1/2" Correction for Iron Deck if required..... - 3 1/2" 8' 8" Other Corrections (if any)..... ✓
Length x Height. State if open or closed at ends. Forecastle x Complete shelter deck Bridge..... x with poop deckhouse on top Poop 61' 5" x 4' 6" } Closed steel bhd at fore end openings closed by stormboards at after end						Winter Freeboard..... 8' 8" Summer Freeboard 8' 2" Indian Summer Freeboard..... 4' 8" N. A. Winter Freeboard..... ✓ Correction necessary because clearside amidships measured in accordance with the Statute is not taken at intersection of the wood or steel deck with side } Nil.
Winter Freeboard from Deck Line 8' 8" Summer " " " 8' 2" Indian Summer " " " 4' 8" N. A. Winter " " " ✓						

110 APR 1932

1m, 2.32

MARKING FORM
[1] SEP 1955
RECEIVED

MARKING FOR
123 NOV 1955
RECEIVED

MARKING FORM
RECEIVED 18 APR 1934

116 APR 1934 Register
Foundation