

Port of Survey Belfast
Date of Survey October 1916
Name of Surveyor _____

Ship's Name.	Port of Registry and Nationality.	Official Number.	Gross Tonnage.	Date of Build.	Particulars of Classification.
Island & Wolff No 509					100A.1. Awning deck with freeboard contemplated

Moulded Depth as measured 34' 10" Main Deck.
 " " " 43' 7" Spar or Awning Deck.

NOTE.—If the depth is measured when vessel is afloat, the details of measurement should be reported.

10-efficient of fineness 79
 any modification necessary } Cell D.B. rising 3" at side
 [Para. 4 (a) to (e)*]
 10-efficient as corrected 77 if British tonnage given

Allowance for strength in excess of Lloyd's rules =

tate particulars—

Three complete steel deck
strengthened top sides
Deep channel framing
web frames and stringers
Eight W.T. bulkheads to awning deck

keel at Stem 102 } at $\frac{1}{2}$ length from Stem 53- }
 Sternpost... 30 } 66 mean " " " Sternpost... 9 } 32 mean
 Drop in Sheer abaft amidships..... 3"

Awning
 ound of Spar-deck Beam..... 9"
 „ „ Main-deck „ 9"

	Length	×	Height.	State if open or closed at ends.
breastplate		×		
ridge		×		
pop		×		

EEBOARD recommended amidships from centre of Disc to top of Statutory Deck Line, Wood (~~Iron~~) Deck:—Awning 12' .. 1

Fresh Water Line	above centre of Disc	8
Indian Summer Line	" "	" "	8
Winter Line	below	" "	8
Winter North Atlantic Line	" "	" "	7

NOTE.—All vessels equal in strength to Lloyd's Spar-decked rule, or which, although in excess of that rule, do not come up to Lloyd's requirements for Ships of full scantlings to the upper deck, are to be considered as Spar-decked Ships, the freeboard for which will vary with their strength.

All vessels equal in strength to Lloyd's Awning-decked rule, or which, although in excess of that rule, do not come up to Lloyd's requirements for a Spar-decked Vessel, are to be considered as Awning-decked Ships, the freeboard for which will vary with their strength.

* If the frames, skin planking, or ceiling are of unusual thickness the breadth of vessel to inside of ceiling should be reported if possible.

ts for a Spar-

W450-017