

5/6 Lennart ex Driva

Cable to Malmo

Steamer Lennart if openings made bridge front with class B closing appliances portable plates with hook bolts freeboard required two feet two inches from statutory line $1\frac{1}{4}$ inches above wood deck side fresh 4 Indian Winter $2\frac{1}{2}$ Atlantic 6 inches

In confirming cable the Surveyor should be informed that if openings are made in the bridge front with temporary means of closing as proposed, the bunker hatches in the main deck under the bridge should have coamings fitted nine inches in depth with covers and battening down arrangements as required by the rules

E.W.B.

24. 1. 21



© 2019

Lloyd's Register
Foundation

W451-0148