

REPORT ON ELECTRIC LIGHTING INSTALLATION. No. 28299

Port of SUNDERLAND Date of First Survey Feb. 24 Date of Last Survey Mar 11 '22 No. of Visits 6
 No. in Reg. Book on the Iron or Steel "BLYTHMOOR" Port belonging to London
 Built at Sunderland By whom William Dorriford & Sons Ltd. When built 1922
 Owners' Address Newcastle, on Tyne
 Yard No. 551 Electric Light Installation fitted by Clarke Chapman & Co. Ltd. When fitted 1922

DESCRIPTION OF DYNAMO, ENGINE, ETC.

One single cylinder direct acting open type vertical engine direct coupled to a continuous current compound wound dynamo

Capacity of Dynamo 85 Amperes at 100 Volts, whether continuous or alternating current continuous

Where is Dynamo fixed In Engine Room Whether single or double wire system is used Double

Position of Main Switch Board near Dynamo having switches to groups A, B, C & D of lights, &c., as below

Positions of auxiliary switch boards and numbers of switches on each Each lighted group of lights provided with switches as required

If fuses are fitted on main switch board to the cables of main circuit Yes and on each auxiliary switch board to the cables of auxiliary circuits Yes and at each position where a cable is branched or reduced in size Yes and to each lamp circuit Yes

If vessel is wired on the double wire system are fuses fitted to both flow and return wires or cables of all circuits including lamp circuits Yes

Are the fuses of non-oxidizable metal Yes and constructed to fuse at an excess of 50% per cent over the normal current

Are all fuses fitted in easily accessible positions Yes Are the fuses of standard dimensions Yes If wire fuses are used are permanent instructions fitted on or near each switch board giving particulars of proper size of fuse for each circuit Yes

Are all switches and fuses constructed of incombustible materials and fitted on incombustible bases Yes. slate & porcelain

Total number of lights provided for 140 arranged in the following groups:—

Total number of lights provided for						
A Saloon	56	lights each of	16	candle power requiring a total current of	31.3	Amperes
B Engine Room	56	lights each of	16	candle power requiring a total current of	31.3	Amperes
C Engine Room	28	lights each of	16	candle power requiring a total current of	15.7	Amperes
D Wipers	-	lights each of	-	candle power requiring a total current of	25	Amperes
E	—	lights each of	-	candle power requiring a total current of	-	Amperes
2	Mast head light with	1	lamps each of	32	candle power requiring a total current of	2.2 Amperes
2	Side light with	1	lamps each of	32	candle power requiring a total current of	2.2 Amperes
6	Cargo lights of	6 - 16		candle power, whether incandescent or arc lights <i>Incandescent</i>		

If arc lights, what protection is provided against fire, sparks, &c.

Where are the switches controlling the masthead and side lights placed In Wheel House

DESCRIPTION OF CABLES.

Main cable carrying	85	Amperes, comprised of	19	wires, each	14	S.W.G. diameter, .094	square inches total sectional area
Branch cables carrying	31.3	Amperes, comprised of	7	wires, each	17	S.W.G. diameter, .017	square inches total sectional area
Branch cables carrying	15.7	Amperes, comprised of	7	wires, each	18	S.W.G. diameter, .0125	square inches total sectional area
Leads to lamps carrying	1.6	Amperes, comprised of	1	wires, each	18	S.W.G. diameter, .0018	square inches total sectional area
Cargo light cables carrying	3.3	Amperes, comprised of	168	wires, each	38	S.W.G. diameter, .0050	square inches total sectional area

DESCRIPTION OF INSULATION, PROTECTION, ETC.

Vulcanized india rubber lapped & braided & lead covered where exposed steel armored cable

Joints in cables, how made, insulated, and protected No joints except mechanical ones

Are all the joints of cables thoroughly soldered, and the flux used not containing acids or other corrosive substances Yes Are all joints in accessible positions, none being made in bunkers, cargo spaces, or spaces which may at any time be used for carrying cargo, stores, or baggage Yes

Are there any joints in or branches from the cable leading from dynamo to main switch board No

How are the cables led through the ship, and how protected Lead & armored cables run in ducts & lapped to deck with string galvanised iron clips



© 2020
Lloyd's Register
Foundation

W654-0011

DESCRIPTION OF INSULATION, PROTECTION, ETC.—continued.

Are they in places always accessible *no* ✓

What special protection has been provided for the cables in open alleyways or where exposed to weather or moisture *lead covered & steel armored cables* ✓

What special protection has been provided for the cables near galleys or oil lamps or other sources of heat *lead & armored cables* ✓

What special protection has been provided for the cables near boiler casings " " " ✓

What special protection has been provided for the cables in engine room " " " ✓

How are cables carried through beams *In lead bushes* ✓ through bulkheads, &c. *in HT glands* ✓

How are cables carried through decks *In galvanizing in deck tiles* ✓

Are any cables run through coal bunkers *yes* or cargo spaces *yes* or spaces which may be used for carrying cargo, stores, or baggage *yes* ✓

If so, how are they protected *lead covered & steel armored cables* ✓

Are any lamps fitted in coal bunkers or spaces which may at times be used for cargo, coals, or baggage *no* ✓

If so, how are the lamp fittings and cable terminals specially protected -

Where are the main switches and fuses for these lights fitted -

If in the spaces, how are they specially protected -

Are any switches or fuses fitted in bunkers *no* ✓

Cargo light cables, whether portable or permanently fixed *portable* ✓ How fixed *to HT connection boxes* ✓

In vessels fitted on the single wire system, how is the dynamo terminal fixed to the hull of vessel *Double wire system* ✓

How are the returns from the lamps connected to the hull -

Are all the joints with the hull in accessible positions -

Is the installation supplied with a voltmeter *yes* ✓, and with an amperemeter *yes* ✓, fixed *on Switchboard* ✓

VESSELS BUILT FOR CARRYING PETROLEUM

In vessels built for carrying petroleum, are all switches and fuses fitted in positions not liable to the accumulation of petroleum vapour or gas -

Are any switches, fuses, or joints of cables fitted in the pump room or companion -

How are the lamps specially protected in places liable to the accumulation of vapour or gas -

The copper used is guaranteed to have a conductivity of not less than that of the Engineering Standards Committee's standard, and the wires are protected by tinning from the sulphur compounds present in the insulating material.

Insulation of cables is guaranteed to have a resistance of not less than *600* megohms per statute mile at 60° Fahrenheit after 24 hours' immersion in water, the test being made after one minute's electrification at not less than 500 volts and while the cable is still immersed.

The foregoing statements are a correct description of the Electric Light installation fitted by us on this vessel and we declare that it is at this date in good order and safe working condition.

For Clarke, Chapman & Co. Ltd.

Electrical Engineers

Date *March 16th 1922*

COMPASSES.

H. Walker Chairman Distance between dynamo or electric motors and standard compass *120 ft*

Distance between dynamo or electric motors and steering compass *114 "*

The nearest cables to the compasses are as follows:—

A cable carrying	Amperes	feet from standard compass	feet from steering compass
<i>1.1</i>	<i>12</i>	<i>6</i>	<i>6</i>
<i>1.1</i>	<i>6</i>	<i>12</i>	<i>12</i>
<i>-</i>	<i>-</i>	<i>-</i>	<i>-</i>

Have the compasses been adjusted with and without the electric installation at work at full power *yes* ✓

The maximum deviation due to electric currents, etc., was found to be *nil* degrees on *all* course in the case of the

standard compass and *nil* degrees on *all* course in the case of the steering compass.

WILLIAM DOXFORD & SONS, Limited.

Builder's Signature.

Date

GENERAL REMARKS.

The electric light installation for this vessel has been fitted in a satisfactory manner and in accordance with the rules.

It is submitted that this vessel is eligible for THE RECORD.

See £8.

14/3/00. Paid 16/3/00

Committee's Minute

22/3/22 Surveyor to Lloyd's Register of Shipping.



© 2020

Lloyd's Register Foundation

THE SURVEYORS ARE REQUESTED NOT TO WRITE ACROSS THIS MARGIN.