

COPY.

Lloyd's Register of Shipping,

71, Fenchurch Street, E.C.3.

This Society is not in a position to state the increase in draught due to 13th August, 1937. and with regard to the amended tonnage, this is a matter for the

Dear Sirs, of or Greek Government authorities.

I beg to acknowledge the receipt of your letter of the 11th instant regarding the s.s. "KONSTANTINOS HADJIPATERAS" and in reply have to inform you that if the tonnage opening in the shelter deck of this vessel is permanently closed by riveted plates or converted into an ordinary hatchway having Rule height coaming, covers, tarpaulins and battening arrangements, the freeing port in the tonnage well and all overboard scuppers draining the shelter tween decks are permanently closed by riveted plates, the tween deck space being drained in lieu thereof by scupper pipes led to the bilges, any sanitary discharges draining spaces situated below the shelter deck are fitted with two automatic non return valves, or one automatic non return valve with positive control from above the shelter deck, the side fore and afters in No.3 hatchway on the shelter deck be fitted with reverse mounting angles 3 x 3 x .38, and the sills of the doors giving access to the crew's quarters aft and in the exposed machinery casings on the shelter deck be increased in height to 24", a freeboard corresponding to an increase in draught of about 25" could be assigned.



Lloyd's Register

Foundation

WFOH 133 (1/2)

COPY.

-2-

This Society is not in a position to state the increase in deadweight due to the deeper immersion, and with regard to the amended tonnages, this is a matter for the Board of Trade or Greek Government Authorities.

If the Owners decide to convert the vessel to a closed shelter decker I shall be obliged if you will kindly advise Office at what port this will be done in order that the necessary instructions in the matter may be sent to the Society's local Surveyors.

I am, Dear Sirs,

Yours faithfully,

Assistant Secretary.

Messrs. C. Michalos & Co., Ltd.,
40, St. Mary Axe,
E. C. 3.



© 2020

Lloyd's Register
Foundation

WHS4-9133 (2/2)