

1m, 11.29.

W454-0297

FREEBOARD REPORT on the

LED BURY.

It is submitted the Freeboards given on the accompanying form, being those required by the Tables, merit approval, the same to be marked on the vessel's sides, inserted in the certificate of classification, and recorded in the Register Book, *subject to*

- (1) The steel covers on the port & starboard feedly gratings being permanently attached
- (2) all coaling and trimming hatches on the freeboard deck being fitted with 9" coamings and efficient cover, lat paulans and battening appliances
- (3) The cleats on the freeboard deck cargo hatchways being spaced not more than 24" apart
- (4) Air pipes on superstructure deck being fitted with closing appliances
- (5) Wood plugs or other efficient means being fitted to the overhead scuppers from the shelter tween decks to prevent the admission of water to that space.

W.B. on file
22.4.32
Convention