

not got into the tanks yet.

Wh54-0324

2  
1/2

REPORT on the

S.S. "Podesta" ex "Odessa"

The surveyor should be informed that to make the hatchway ~~its~~ on the Shelter Deck equivalent to the rule requirements transverse webs should be fitted in each of the four cargo hatchways between existing webs of plate 12" x 30" with double angles 3 1/2 x 3 x 42 top and bottom, or other equivalent section may be used.

If the spacing of the web plate beams in the upper Deck cargo ways is the same as on the Shelter Deck similar web plate will be required at these hatchways.

It is concluded that efficient bulkheads are fitted in the tween decks at the ends of the tonnage opening; that the <sup>if any</sup> ~~in~~ these bulkheads are closed by storm boards fitted in channels the full height of the bulkhead; and that temporary covers are fitted over the tonnage opening required by the Rules for Shelter Deck Steamers, but the surveyor should confirm this.

*This part complied with  
Port Land Lr. 20/6/21*

*OK*

*ERM*

*W.B.*

Lloyd's Register  
Foundation