


FREEBOARD REPORT on the S. S. BOWLING

It is submitted the Freeboards given on the accompanying form, being those required by the Tables, merit approval. Subject to

- ① The air tubes on the foreboard deck being increased to a height of 36" to the openings, and the air tubes to the double bottom on the raised quarter deck being increased to a height of 30" to the openings.
- ② The openings in the air tubes being provided with efficient closing appliances.
- ③ a gangway, lifelines, or other satisfactory means of protection for the crew being fitted in the fore well.
- ④ The freeing port area in the bulwarks on the raised quarter deck being increased to an area of $24\frac{1}{4}$ sq ft on each side of the ship.
- ⑤ The openings in the coal hatch trunk being fitted with strong steel covers capable of being securely closed, if this is not already the case.

Convention

Approved
As sh/s 3/5/32



© 2020
Lloyd's Register
Foundation
3-May-32