

FREEBOARD REPORT on the

M. S. Malini

Freeboard as a C.S.S. vessel - 6" from 2nd deck.
 Corresponding draught $13'-0\frac{1}{2}"$ ✓

Freeboard as a FS vessel. = $3'-1\frac{1}{4}"$
 Corresponding draught $16'-11\frac{1}{2}"$ ✓
 Differ $3'-10\frac{3}{4}"$ ✓
 60% difference $2'-4"$ ✓

Draught allowed $15'-4\frac{1}{2}"$ ✓

Corresponding fbd $4'-10\frac{1}{2}"$ from wood deck.

depth
 str

$$\begin{array}{r}
 20'-0" \\
 \quad \frac{1}{2} \\
 \quad 2\frac{1}{2} \\
 \hline
 20-3" \\
 15-4\frac{1}{2} \\
 \hline
 4-10\frac{1}{2}
 \end{array}$$

from wood deck.



© 2020

J. M. M.

Lloyd's Register
 Foundation

W458-0051

W458-0053