

Single Screw Steamer No. 289 proposed to be built by Messrs.  
A/S Fredriksstad Mek. Verksted with a view to class 100A1 "With  
Freeboard" "Strengthened for Navigation in Ice".  
-----

Rule Dimensions:- 358' x 57' x 35' to upper deck  
23.5' to second deck.

Scantling Nos:- 11277 and 31683

Proportions:- Length = 10.2 depths to upper deck.  
-----

Plans of midship section, profile and decks, shell  
expansion and bulkheads submitted, in triplicate, by the Oslo  
Surveyors.

This vessel is a sister vessel to the same Builders'  
Yard No. 287, the plans for which were approved on the 16th  
March last.

It is submitted that provided

Compliance

the vessel will be eligible to be classed 100A1 with a freeboard  
corresponding to a draught not exceeding that contemplated by  
the Rules for a complete superstructure vessel having a tonnage  
opening, with the notation "Strengthened for Navigation in Ice".  
Steel Note.

The vessel is of a length to require six watertight  
bulkheads to be fitted. It is observed from the plans, however,  
that the bulkhead required to be fitted between the engine room  
and the after peak bulkhead is proposed to be omitted.  
Compensation for the omission of this bulkhead has been  
indicated on the plans ~~in the form of a deep web, or, alter~~  
<sup>by increasing the</sup> ~~natively, the~~ framing throughout this hold ~~increased~~ by  $1\frac{1}{2}$  m/m  
in thickness. It is submitted the Surveyors be informed that  
the Special Survey of the vessel during construction may be  
proceeded with, but before she is finally classed in the Register  
Book it will be necessary for a letter to be furnished by the  
Owners desiring the omission of the bulkhead in question, in  
the terms of Section 17, Paragraph 2(c) of the Rules.

If this be done a notation will be made in the Register  
Book in respect of the bulkheads as follows :-

W 46-0136(112)



"Intermediate BH in after hold dispensed with; 5 BH."

*[Handwritten signature]*

*[Handwritten signature]*

4. 5. 37.

*[Handwritten initials]*

*[Handwritten initials]*

*[Handwritten note]* to 4/5.

Ltr. 30.4.37.  
Ansd. 4.5.37.  
8 plans 4 retained



© 2019

Lloyd's Register  
Foundation

WVG-0361213