

EXTRACT FROM COPENHAGEN REPORT No. 9895. RECD. 15.5.36.

s.s. "SCOTIA".

Alteration of No. 4 hatchway on trunk top:-

The hatch has been increased in height from about 12" to 3'-6". New coamings of .44 steelplates with 5" x 5" x  $\frac{1}{2}$ " foot angles and 9" x  $3\frac{1}{2}$ " x  $\frac{7}{16}$ " bulb angle horizontal stiffening bar on sides and ends supported by .44 brackets with  $3\frac{1}{2}$ " flanges spaced not more than 10'.

The hatch coamings etc. have been strongly constructed and efficiently supported etc., also the old webs and supports have been used again.

*new Tonnages*  
Quoos: 2400. U.D. 1877. Net 1400

*Noted*

*[Signature]*

*23/5/36.*

RETAIN



© 2020

Lloyd's Register  
Foundation

W463-0019