

W467-0307

RD REPORT on the S.S. "Hillbrook".

It is submitted the surveyors be informed that from the particulars available in this Office for a sister-ship to the S.S. "Hillbrook" the scantlings of the hatch supports are as follows:-

<u>No. 1.</u>	Hatchway.	1 Web 19" x 36" with 4" x 3" x 54" mounting angles.
		1 Web @ 18" x 36", 1 @ 17" x 36", & 1 @ 16" x 36" with 4" x 3" x 44" angles.
<u>No 2</u>	do.	Mounting angles 5" x 3" x 46".
<u>No 3</u>	do.	do. do. 5" x 3" x 42".
<u>No 4</u>	do.	1 Web 19" x 36", 1 @ 18" x 36" & 1 @ 17" x 36" with 4" x 3" x 44" angles.

The surveyors will notice that ~~the~~ particulars of the ~~beam~~ supports given by them for the S.S. "Hillbrook" are slightly less than given above and also slightly less than required by the Rules and they should be asked to confirm their figures.

At the same time the surveyors should verify the marking, and forward the usual verification form for the issue of new Certificates. The official number should be reported thereon.

W467-0314