


EEBOARD REPORT on the

S.S. Doric Star

It is submitted the Newcastle Surveyors be requested to forward full particulars on report C II for keelboard reassignment, if the owners' proposal to increase the length is proceeded with.

The builders Messrs. Palmers should be informed that it is not considered that the proposed increase in length will greatly affect the vessel's keelboard, but that, if a provisional reassignment is desired, they should forward particulars of the new length on the loadline, the new moulded depth at the middle of this length, the sheer at each sixth of the new length, the new length of fore-castle, and the moulded displacement at a moulded draught equal to 85% of the new moulded depth.



© 2019

Lloyd's Register  
Foundation

W468-0057