

Palmers Hebburn Company, Limited.

Shipbuilders, Ship and Engine Repairers, Boiler Makers, Ironfounders &c.

Largest Graving Dock on North-East Coast.

TELEGRAMS: PALMERS, HEBBURN.

TELEPHONES { JARROW 67136.
HEBBURN 44.

Registered Office—

HEBBURN-ON-TYNE.

CO. DURHAM.

HNS/EMJ.

Ref. G.M. Dept.

14th November, 1933.

Lloyd's Register of Shipping,
71, Fenchurch Street,
LONDON, E.C.3.



Dear Sirs,

S.S. "Doric Star".

Further to our submission of the 7th instant, in connection with new hatch webs at upper deck, approved by you per letter of the 10th instant, we now require greater clearance between bottom of web at centre and top of insulated plugs, and accordingly submit for your consideration the following alternative scantlings which give equivalent sectional modulus :-

Approved Scantlings.		Alternative Scantlings.	
(1) Plate	11" x .35"	Plate	8" x .50"
Angles	4 @ 4" x 3" x .44"	Angle	4 @ 6" x 3" x .50" OA.
(2) Plate	11" x .40"	Plate	8" x .54"
Angles	4 @ 4" x 3" x .54"	Angles	4 @ 7" x 3" x .54" OA.
(3) Plate	11" x .35"	Plate	8" x .52"
Angles	4 @ 4" x 3" x .50"	Angles	4 @ 6½" x 3" x .52" OA.

As we are in consultation with the Owners to-morrow when this question will be discussed, we should be glad if you would please wire a reply to reach us in time for the discussion.

We are,

Yours faithfully,

For the Company.

Lloyd's Register
Foundation

W468-011

Referred to the Chief Ship Surveyor,

15 NOV 1937
WIRE REQUESTED.

[Handwritten signature]

СЕРВИСЪ ВЪЗДУШНОГО
ТРАНСПОРТА
МОСКВА

МАРШРУТЪ
САНКТ-ПЕТЕРБУРГЪ-ТАШКЕНТЪ



© 2019
Lloyd's Register
Foundation

Великобританская
Компания
Ллойдс