


FREEBOARD REPORT on the

S/S Antonios Vrondissis

It is submitted the Freeboards given on the accompanying form, being those required by the Tables, merit approval, subject to:-

- ① The wood fore-and-afters of bunker hatchways on Bridge and Freeboard Decks being renewed to Convention requirements, and hatchway beams, fore-and-afters, battens and cleats being overhauled where necessary to Surveyor's satisfaction.
- ② Hatch cover bearing surfaces, where less than 2 inches in width, being increased to comply reasonably with the Convention.
- ③ An additional topauler being provided for the Nettle Hatch on the Bridge Deck.
- ④ Broken side scuttle glasses in Forecastle space being renewed.

Greek Convention.

Ass'tlts
Owner & P.W.
9.10.33
 LR
S.R.P.

© 2019
R.P. 7.10.33
Lloyd's Register
Foundation
W468 - 0258