

COPY.

# Lloyd's Register of Shipping.



Port LONDON,

8th December, 1938.

This is to Certify that

J. L. SMITH,

the undersigned Surveyor to this Society did at the request of the Owners' Representative attend on board the S.S. "CANTABRIA" 5649 tons gross of Santander, on the 28th October, 1938, and subsequently, whilst in Millwall Dry Dock, for the purpose of ascertaining the nature and extent of machinery damage stated to have been sustained by vessel grounding in River Thames, off Stoneness Point on 3rd October, 1938, whilst on a voyage from Igarka to London with a cargo of timber.

It was ascertained from the log books that the vessel grounded on Stoneness Point, River Thames, and after attempting to refloat vessel by her own engine power was ultimately refloated with the assistance of a Tug and engines combined.

For further particulars of engine movements during refloating operations please see log books.

The vessel was examined in drydock and the following was:-

FOUND

Wear down of screwshaft in stern bush excessive.

RECOMMENDED

Screwshaft to be drawn in for examination and stern bush rewooded. Screwshaft found fractured at forward end of keyway. Spare shaft to be fitted, Lignum vitae in lower half of stern bush excessively worn to be renewed. Sea cocks and valves to be opened up for examination and necessary repairs due to stated grounding to be effected.

The above recommendations were made with a view to placing the machinery of the vessel in as good and efficient condition as it was in prior to the alleged casualty.

*J. L. Smith*  
Surveyor to Lloyd's Register  
of Shipping.

This Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that:-

"While the Committees of the Society use their best endeavours to ensure that the functions of the Society are properly executed, it is to be understood that neither the Society nor any Member of any of its Committees is under any circumstances whatever to be held responsible for any inaccuracy in any report or certificate issued by the Society or its Surveyors, or in any entry in the Register Book or other publication of the Society, or for any error of judgment, default or negligence of any of its Committees or any Member thereof, or the Surveyors, or other Officers or Agents of the Society."