



# Lloyd's Register of Shipping,

Midland Bank Chambers,

Newport, Mon. 12th October, 1932.

ENCLOSURE  
LLOYD'S REGISTER  
RECEIVED

13 OCT 1932

Ans. 13/10

LONDON

We herewith enclose freeboard verification form for steamer "GLANRHYD", and with reference to the assignment of the 16th April last, we have to state that all the requirements as indicated therein have now been carried out as follows:-

The cross bunker hatch on the upper deck in bridge space now fitted with 3" wood covers and two tarpaulins fitted to this hatch and four escape hatches, with battens and wedges.

Ventilator coamings now fitted with wood plugs and canvas covers.

Air pipes 7½" high now increased to 36" to the openings, and fitting holes drilled in the upper part of the bend of air pipes, and 12" in height.

Wood plugs now fitted to all air pipes.

Lifelines now fitted in forward well for the protection of crew.

Portable plates in the bridge front now fitted with bolts passing through bulkhead and plate, spaced about 6" apart.

We shall be pleased if you will forward the new Convention Freeboard Certificates by return of post.

We are, Sir,  
Yours faithfully,  
The Surveyors,

per.

*W. A. Farlow*

Secretary,  
LONDON.

© 2020

Lloyd's Register  
Foundation

0471-0240



Referred to the Chief Ship Surveyor.  
(Freeboard).

3 OCT 1932

*Particulars of alterations noted in Report.  
It is submitted the Certificate be forwarded  
to the Transport Commissioners for issue*

*13/10/32*

© 2020

Lloyd's Register  
Foundation