

51384  
GROS  
Steel Screw Motor Vessel "GROSHOLM", No. 22297 in the Register Book; built by Messrs. Akt. Rodby Havns Jernskibsværft, in 1920; class 100A1; Owners Skibs A/S Grimstad (W.B. Markussen, Manager).

Dimensions:- 247' x 40' x 23.66'

This vessel is at present under Survey at Oslo, where alterations are being effected to enable the vessel to carry whale and herring oil.

A letter has been received from the Oslo Surveyors enclosing a plan, in triplicate, showing the flensing structure proposed to be fitted in the forward well.

It is submitted that provided the arrangements be carried out as shown and amended on the plan and to the Surveyors' satisfaction, the same will merit approval.

The Surveyors should be informed that the erection has been considered ~~generally~~ on the basis of its being a light covering for the blubber boilers, etc., and that the scantlings and arrangements, including the riveting of the ends, could be approved on that basis. Their attention should, however, be drawn to the fact that if this deck will have to support <sup>any local</sup> weights of appreciable magnitude, they should satisfy themselves that the scantlings of the deck and of the side stringing and frames are sufficient for this purpose.

The Surveyors should also be informed that the equipment grade changes, and if the figure 1 is desired to be retained, the equipment should be in accordance <sup>or equivalent to</sup> with the requirements of the Rules.



© 2019  
3. 10. 29.

Lloyd's Register  
Foundation

W473-0092